



**EDWARD B. WALSH & ASSOCIATES, INC.**  
*Complete Civil Engineering Design / Consultation Services*  
Lionville Professional Center  
125 Dowlin Forge Road  
Exton, PA 19341

July 26, 2018

Mr. Will Ethridge, AICP  
Director of Planning and Zoning Administrator  
Westtown Township  
1039 Wilmington Pike  
West Chester, Pa. 19382

Re: Preliminary/Final Plan for Cahill subdivision  
Westtown Township  
EBWA No. 4062

Dear Will;

The following letter is being written to accompany the resubmission of the above referenced project. We have revised the plans in accordance with the July 11, 2018 letter from McCormick Taylor and the July 17 email from Bill Malin of Carrol Engineering. This letter's enumeration follows that of the consultant's letters.

### **McCormick Taylor Review Comments**

#### **Waivers**

A waiver request from Section 149-600 to consider the plan preliminary and Final has been added to sheet 1.

#### **Zoning**

1. Note 8 has been added to sheet 1 requiring the signed and sealed statement to be submitted with the building permit application. It seems to be more appropriate with that submission as it will include the final house layout and grading, as it may be less than what currently is presented.

#### **Subdivision and Land Development**

2. The zoning data table on sheet one reflects the contiguous lot area.

*REGISTERED PROFESSIONAL ENGINEERS & LAND SURVEYORS*  
*Pennsylvania, New Jersey, Delaware, Maryland & North Carolina*  
610-903-0060 FAX 610-903-0080  
[www.ebwalshinc.com](http://www.ebwalshinc.com)  
Established 1985

3. We have requested a waiver to allow the plan to be considered both preliminary and final.
4. We have added a curb detail to sheet 8 and specified the Penn DOT 408 requirement in note 9 on sheet 1.
5. A driveway profile has been added to sheet 8.
6. We have added concrete apron to the driveway, however there is no sidewalk proposed on this side of Piper Lane as the grading necessary to install the sidewalk would require the construction of a retaining wall along the Cahill frontage.
7. The location of the existing sanitary sewer has been added to the plan.

### **Stormwater Management**

8. We met with Kevin Matson and reviewed the Stormwater design and grades and we believe that he will concur that the stormwater and grading is acceptable.
9. The stormwater report has been revised. There is only one rain garden. The rain gardens will be seeded with wetland grass mix. No planting other than the grasses are proposed.
10. The blanket easement for stormwater is offered in the owner's certification on sheet 7.
11. The added the contours on Piper Lane that represent the grades proposed and contracted.
12. There are no berms proposed along Piper Lane. The grading was revised and submitted for review and approval along the Cahill property prior to construction of the road as an easement was obtained to grade on that property. Since then an agreement of sale was reached with Mr. Cahill and the new lot is proposed to be created. The new plan represents the final grading proposed along Piper Lane. We have submitted a composite grading and site plan that shows how all of the different plans come together.
13. We believe that the sequence of construction shown on the E&S plan is how this lot will be constructed. The road, curb and utilities are already in place. We discussed this with Kevin Matson and I believe it felt it was acceptable.

### **General Comments**

14. The Legal descriptions are attached.
15. The site is to be filled with on-site spoils form the Westtown Woods subdivision. My client is fully aware of this and we discussed this with Kevin and he concurred that a cut and fill analysis is not necessary.
16. Lot 2 will be added to the homeowners Association for Westtown Woods. We added note 10 to sheet 1 specifying this.

17. Mr. Malin has been consulted during the installation of thru force main in Piper Lane so that stubs could be installed. He responded via e-mail that the plans do not affect the sewer line. See comment 10 above.
18. We revised the detail to show SuperPave.
19. We added a driveway apron detail and graphically showed it on the revised plan.
20. The property markers for the lots are already installed.
21. To be taken care of by others.

### **Carroll Engineering Review**

#### **Sanitary Sewer**

1. We added the location of the existing sewer main to the profile.
2. The Piper Lane profile has not changed so no adjustment is necessary.

I believe we have incorporated all of the concerns and issues raised and discussed within this submission. Should you have any questions or need any additional information please contact me.

Very Truly Yours  
Edward B. Walsh and Associates, Inc.



Andrew Eberwein  
Enc.

**POST-CONSTRUCTION  
STORMWATER MANAGEMENT REPORT  
AND NARRATIVE  
FOR  
SUBDIVISION PLAN**

**FOR**


**PARCEL 67-4F-73**

**PREPARED BY**



**EDWARD B. WALSH & ASSOCIATES, INC.  
125 DOWLIN FORGE ROAD  
LIONVILLE PROFESSIONAL CENTER  
EXTON, PA 19341  
610-903-0060  
EBWA FILE NO. 4062**

**MAY 24, 2018  
7/26/18**



Project Narrative:

Southdown Homes is proposing a two lot subdivision of the Cahill property in Westtown Township. Construction will consist of a one single family house, driveway and stormwater management facilities. All lots will have public sewer and water.

Existing Features:

The sites existing coverage consists of mainly fallow. There are no wetlands or streams on this site. The site drains to the Plum Creek which and the classification of the watershed is WWF-MF. The soils classifications for the site are UrLD and GDB.

Post Construction Stormwater Management:

The stormwater management was designed using the Rational method. The site was designed so that the post developed peak discharge does not exceed the predeveloped peak discharge rate for the 2 year, 10 year, 25 year 50 year and 100 year and further reducing the 2 year post to the 1 year pre. For peak rate control a subsurface infiltration bed and rain garden were added.

Peak Rate Control:

	<u>Pre</u>	<u>Total Post</u>
1	.54	.46
2	.642	.54
5	.751	.639
10	.827	.704
25	.918	.781
50	.977	.831
100	1.037	.883

Infiltration:

Infiltration Tests were performed on the lot "see Soils Report for Stormwater Recharge Suitability" for test results. Worksheet #4 was used to for the 2 yr pre to post volume increase. The volume needed for infiltration is 1345 c.f. the volume provided for infiltration is 1488 c.f. A subsurface infiltration bed and a rain garden are used to obtain this number.

Erosion and Sedimentation Control:

Erosion and sedimentation control has been designed to prevent sediment laden stormwater from conveying off the site and into undisturbed areas. A rock construction entrance and silt sock was added.

### Conveyance System

The cross pipe under Piper Lane is being extended through the site to a double inlet. The design conveys the 100 year storm that was used in the design of the original Piper Lane culvert design and that used for the Ballester Subdivision.

**ENTIRE PROJECT AREA**

**WORKSHEET 4. CHANGE IN RUNOFF VOLUME FOR 2-YR STORM EVENT**

PROJECT: Cahill Property  
 Drainage Area: 0.51 acres  
 2-Year Rainfall: 3.2 in  
 Total Site Area: 0.51 acres  
 Protected Site Area: 0.00 acres  
 Managed Area: 0.00 acres

**Existing Conditions:**

Cover Type / Condition	Soil Type	Area (sf)	Area (ac)	CN	S	la 0.2*s	Q Runoff <sup>1</sup> (in)	Runoff Volume <sup>2</sup> (ft <sup>3</sup> )
Meadow		22,000	0.51	58	7.24	1.45	0.341	626
Woods	B	0	0.00	55	8.18	1.64	0.251	0
Impervious	B	0	0.00	98	0.20	0.04	2.967	0
Woods		0	0.00	70	4.29	0.86	0.828	0
<b>TOTAL:</b>			<b>0.51</b>					<b>626</b>

**Developed Conditions:**

Cover Type / Condition	Soil Type	Area (sf)	Area (ac)	CN	S	la 0.2*s	Q Runoff <sup>1</sup> (in)	Runoff Volume <sup>2</sup> (ft <sup>3</sup> )
Lawn	B	16,500	0.38	61	6.39	1.28	0.444	610
Woods	B	0	0.00	55	8.18	1.64	0.251	0
Impervious	B	5,500	0.13	98	0.20	0.04	2.967	1360
Lawn		0	0.00	74	3.51	0.70	1.038	0
Gravel		0	0.00	89	1.24	0.25	2.082	0
Impervious		0	0.00	98	0.20	0.04	2.967	0
<b>TOTAL:</b>			<b>0.51</b>					<b>1,971</b>

**2-Year Volume Increase (ft<sup>3</sup>): 1,345**

2-Year Volume Increase = Developed Conditions Runoff Volume - Existing Conditions Runoff Volume

1. Runoff (in) =  $Q = (P - 0.2S)^2 / (P + 0.8S)$  where

P = 2-Year Rainfall (in)

S =  $(1000/CN) - 10$

2. Runoff Volume (CF) = Q x Area x 1/12

Q = Runoff (in)

Area = Land Use Area (sq. ft.)

NOTE: Runoff volume must be calculated for EACH land use type/condition and HSGI. The use of a weighted CN value for volume calculations is not acceptable.



**NOAA Atlas 14, Volume 2, Version 3**  
**Location name: West Chester, Pennsylvania, US\***  
**Latitude: 39.9356°, Longitude: -75.5909°**  
**Elevation: 417 ft\***  
 \* source: Google Maps



**POINT PRECIPITATION FREQUENCY ESTIMATES**

G.M. Bonnin, D. Martin, B. Lin, T. Parzybok, M.Yekta, and D. Riley

NOAA, National Weather Service, Silver Spring, Maryland

[PF tabular](#) | [PF graphical](#) | [Maps & aerials](#)

**PF tabular**


<b>PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches)<sup>1</sup></b>										
Duration	Average recurrence interval (years)									
	1	2	5	10	25	50	100	200	500	1000
5-min	0.353 (0.323-0.387)	0.421 (0.385-0.461)	0.492 (0.450-0.538)	0.542 (0.494-0.592)	0.600 (0.544-0.656)	0.639 (0.577-0.699)	0.678 (0.609-0.742)	0.711 (0.635-0.780)	0.748 (0.662-0.824)	0.775 (0.681-0.858)
10-min	0.564 (0.517-0.618)	0.673 (0.616-0.737)	0.788 (0.720-0.861)	0.866 (0.790-0.947)	0.956 (0.868-1.05)	1.02 (0.919-1.11)	1.08 (0.968-1.18)	1.13 (1.01-1.24)	1.18 (1.05-1.30)	1.22 (1.07-1.35)
15-min	0.706 (0.646-0.772)	0.846 (0.775-0.926)	0.997 (0.911-1.09)	1.10 (1.00-1.20)	1.21 (1.10-1.33)	1.29 (1.16-1.41)	1.36 (1.22-1.49)	1.42 (1.27-1.56)	1.49 (1.32-1.64)	1.53 (1.35-1.70)
30-min	0.967 (0.885-1.06)	1.17 (1.07-1.28)	1.42 (1.29-1.55)	1.59 (1.45-1.74)	1.80 (1.63-1.96)	1.94 (1.75-2.12)	2.09 (1.87-2.28)	2.21 (1.98-2.43)	2.37 (2.10-2.61)	2.48 (2.18-2.75)
60-min	1.21 (1.10-1.32)	1.47 (1.34-1.61)	1.82 (1.66-1.99)	2.07 (1.89-2.26)	2.39 (2.17-2.61)	2.63 (2.37-2.88)	2.87 (2.58-3.15)	3.10 (2.77-3.41)	3.40 (3.01-3.75)	3.62 (3.18-4.01)
2-hr	1.44 (1.31-1.59)	1.75 (1.59-1.94)	2.18 (1.97-2.41)	2.51 (2.26-2.77)	2.94 (2.63-3.24)	3.27 (2.92-3.61)	3.61 (3.20-3.99)	3.95 (3.48-4.37)	4.41 (3.83-4.88)	4.76 (4.10-5.29)
3-hr	1.57 (1.42-1.73)	1.90 (1.73-2.10)	2.37 (2.15-2.62)	2.73 (2.47-3.01)	3.21 (2.88-3.54)	3.58 (3.20-3.95)	3.96 (3.51-4.37)	4.35 (3.82-4.80)	4.86 (4.22-5.39)	5.26 (4.52-5.85)
6-hr	1.93 (1.75-2.14)	2.33 (2.12-2.59)	2.90 (2.63-3.22)	3.36 (3.03-3.72)	4.00 (3.58-4.42)	4.51 (4.01-4.98)	5.05 (4.45-5.58)	5.62 (4.89-6.20)	6.40 (5.49-7.10)	7.03 (5.94-7.83)
12-hr	2.35 (2.13-2.63)	2.84 (2.57-3.17)	3.55 (3.21-3.96)	4.14 (3.73-4.61)	5.00 (4.45-5.55)	5.71 (5.04-6.33)	6.49 (5.66-7.20)	7.32 (6.30-8.14)	8.53 (7.19-9.51)	9.54 (7.89-10.7)
24-hr	2.71 (2.50-2.96)	3.27 (3.01-3.56)	4.10 (3.77-4.47)	4.80 (4.40-5.23)	5.80 (5.30-6.31)	6.65 (6.04-7.22)	7.57 (6.83-8.19)	8.55 (7.67-9.26)	9.99 (8.86-10.8)	11.2 (9.83-12.1)
2-day	3.14 (2.89-3.44)	3.80 (3.49-4.15)	4.77 (4.38-5.21)	5.57 (5.10-6.08)	6.70 (6.11-7.31)	7.64 (6.94-8.33)	8.63 (7.81-9.41)	9.70 (8.71-10.6)	11.2 (9.99-12.2)	12.5 (11.0-13.6)
3-day	3.32 (3.05-3.63)	4.00 (3.68-4.37)	5.01 (4.61-5.47)	5.84 (5.35-6.37)	7.01 (6.40-7.65)	7.99 (7.26-8.70)	9.02 (8.15-9.82)	10.1 (9.09-11.0)	11.7 (10.4-12.7)	13.0 (11.5-14.1)
4-day	3.49 (3.21-3.81)	4.20 (3.87-4.59)	5.25 (4.83-5.74)	6.11 (5.60-6.66)	7.33 (6.69-7.99)	8.33 (7.57-9.07)	9.40 (8.50-10.2)	10.5 (9.46-11.5)	12.1 (10.8-13.2)	13.5 (11.9-14.7)
7-day	4.08 (3.79-4.43)	4.89 (4.54-5.31)	6.05 (5.61-6.57)	7.01 (6.48-7.59)	8.37 (7.71-9.06)	9.50 (8.70-10.3)	10.7 (9.76-11.6)	12.0 (10.9-12.9)	13.8 (12.4-14.9)	15.3 (13.6-16.6)
10-day	4.65 (4.33-5.01)	5.55 (5.17-5.99)	6.78 (6.30-7.30)	7.76 (7.21-8.36)	9.13 (8.45-9.82)	10.2 (9.45-11.0)	11.4 (10.5-12.2)	12.6 (11.5-13.5)	14.3 (12.9-15.4)	15.6 (14.0-16.9)
20-day	6.28 (5.89-6.73)	7.46 (6.98-7.98)	8.90 (8.33-9.52)	10.0 (9.37-10.7)	11.6 (10.8-12.4)	12.8 (11.9-13.6)	14.0 (12.9-14.9)	15.2 (14.0-16.3)	16.8 (15.4-18.0)	18.1 (16.5-19.4)
30-day	7.82 (7.37-8.29)	9.22 (8.69-9.78)	10.8 (10.1-11.4)	11.9 (11.3-12.7)	13.5 (12.7-14.3)	14.7 (13.8-15.6)	15.9 (14.8-16.9)	17.0 (15.9-18.1)	18.5 (17.2-19.7)	19.7 (18.2-20.9)
45-day	9.93 (9.42-10.5)	11.7 (11.1-12.3)	13.4 (12.7-14.2)	14.7 (14.0-15.5)	16.4 (15.5-17.3)	17.7 (16.7-18.6)	18.8 (17.8-19.9)	19.9 (18.8-21.1)	21.3 (20.0-22.5)	22.3 (20.9-23.6)
60-day	11.9 (11.3-12.5)	13.9 (13.3-14.7)	15.9 (15.1-16.7)	17.4 (16.5-18.3)	19.2 (18.2-20.2)	20.5 (19.5-21.6)	21.8 (20.6-22.9)	23.0 (21.7-24.2)	24.4 (23.0-25.7)	25.4 (23.9-26.8)

<sup>1</sup> Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS). Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values. Please refer to NOAA Atlas 14 document for more information.


[Back to Top](#)

**PF graphical**





Average recurrence interval (years)
1
2
5
10
25
50
100
200
500
1000



Duration
5-min
10-min
15-min
30-min
60-min
2-hr
3-hr
6-hr
12-hr
24-hr
2-day
3-day
4-day
7-day
10-day
20-day
30-day
45-day
60-day


[Back to Top](#)

**Maps & aerials**

NOAA Atlas 14, Volume 2, Version 3

Created (GMT): Wed Apr 6 19:37:11 2016


**Small scale terrain**



Large scale terrain



Large scale map



Large scale aerial



[Back to Top](#)

---

US Department of Commerce  
National Oceanic and Atmospheric Administration  
National Weather Service  
National Water Center  
1325 East West Highway  
Silver Spring, MD 20910

Questions?: [HDSC.Questions@noaa.gov](mailto:HDSC.Questions@noaa.gov)

[Disclaimer](#)



**NOAA Atlas 14, Volume 2, Version 3**  
**Location name: West Chester, Pennsylvania, US\***  
**Latitude: 39.9356°, Longitude: -75.5909°**  
**Elevation: 417 ft\***  
\* source: Google Maps



**POINT PRECIPITATION FREQUENCY ESTIMATES**

G.M. Bonnin, D. Martin, B. Lin, T. Parzybok, M.Yekta, and D. Riley

NOAA, National Weather Service, Silver Spring, Maryland

[PF tabular](#) | [PF graphical](#) | [Maps & aerials](#)


**PF tabular**

<b>PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches/hour)<sup>1</sup></b>										
<b>Duration</b>	<b>Average recurrence interval (years)</b>									
	<b>1</b>	<b>2</b>	<b>5</b>	<b>10</b>	<b>25</b>	<b>50</b>	<b>100</b>	<b>200</b>	<b>500</b>	<b>1000</b>
<b>5-min</b>	4.24 (3.88-4.64)	5.05 (4.62-5.53)	5.90 (5.40-6.46)	6.50 (5.93-7.10)	7.20 (6.53-7.87)	7.67 (6.92-8.39)	8.14 (7.31-8.90)	8.53 (7.62-9.36)	8.98 (7.94-9.89)	9.30 (8.17-10.3)
<b>10-min</b>	3.38 (3.10-3.71)	4.04 (3.70-4.42)	4.73 (4.32-5.17)	5.20 (4.74-5.68)	5.74 (5.21-6.28)	6.11 (5.51-6.68)	6.46 (5.81-7.08)	6.76 (6.04-7.42)	7.10 (6.28-7.82)	7.33 (6.43-8.11)
<b>15-min</b>	2.82 (2.58-3.09)	3.38 (3.10-3.70)	3.99 (3.64-4.36)	4.38 (4.00-4.79)	4.85 (4.40-5.30)	5.16 (4.65-5.64)	5.44 (4.89-5.96)	5.69 (5.08-6.24)	5.96 (5.27-6.56)	6.13 (5.38-6.78)
<b>30-min</b>	1.93 (1.77-2.12)	2.34 (2.14-2.56)	2.83 (2.59-3.10)	3.18 (2.90-3.47)	3.59 (3.26-3.93)	3.88 (3.50-4.25)	4.17 (3.75-4.57)	4.43 (3.95-4.86)	4.74 (4.19-5.22)	4.96 (4.36-5.49)
<b>60-min</b>	1.21 (1.10-1.32)	1.47 (1.34-1.61)	1.82 (1.66-1.99)	2.07 (1.89-2.26)	2.39 (2.17-2.61)	2.63 (2.37-2.88)	2.87 (2.58-3.15)	3.10 (2.77-3.41)	3.40 (3.01-3.75)	3.62 (3.18-4.01)
<b>2-hr</b>	0.720 (0.652-0.796)	0.876 (0.794-0.968)	1.09 (0.986-1.20)	1.25 (1.13-1.38)	1.47 (1.32-1.62)	1.64 (1.46-1.81)	1.80 (1.60-1.99)	1.97 (1.74-2.18)	2.20 (1.92-2.44)	2.38 (2.05-2.65)
<b>3-hr</b>	0.522 (0.474-0.577)	0.633 (0.575-0.700)	0.790 (0.715-0.872)	0.909 (0.821-1.00)	1.07 (0.959-1.18)	1.19 (1.06-1.31)	1.32 (1.17-1.46)	1.45 (1.27-1.60)	1.62 (1.40-1.79)	1.75 (1.51-1.95)
<b>6-hr</b>	0.322 (0.293-0.358)	0.389 (0.354-0.432)	0.484 (0.439-0.537)	0.561 (0.507-0.621)	0.667 (0.598-0.738)	0.753 (0.670-0.831)	0.843 (0.743-0.931)	0.938 (0.817-1.04)	1.07 (0.916-1.19)	1.17 (0.992-1.31)
<b>12-hr</b>	0.195 (0.177-0.218)	0.235 (0.213-0.263)	0.295 (0.266-0.329)	0.344 (0.309-0.383)	0.415 (0.369-0.460)	0.474 (0.418-0.526)	0.538 (0.470-0.598)	0.608 (0.523-0.676)	0.708 (0.596-0.789)	0.791 (0.655-0.884)
<b>24-hr</b>	0.113 (0.104-0.123)	0.136 (0.126-0.149)	0.171 (0.157-0.186)	0.200 (0.183-0.218)	0.242 (0.221-0.263)	0.277 (0.252-0.301)	0.315 (0.285-0.341)	0.356 (0.320-0.386)	0.416 (0.369-0.451)	0.466 (0.410-0.505)
<b>2-day</b>	0.065 (0.060-0.072)	0.079 (0.073-0.086)	0.099 (0.091-0.109)	0.116 (0.106-0.127)	0.140 (0.127-0.152)	0.159 (0.145-0.173)	0.180 (0.163-0.196)	0.202 (0.181-0.220)	0.234 (0.208-0.255)	0.260 (0.229-0.283)
<b>3-day</b>	0.046 (0.042-0.050)	0.056 (0.051-0.061)	0.070 (0.064-0.076)	0.081 (0.074-0.089)	0.097 (0.089-0.106)	0.111 (0.101-0.121)	0.125 (0.113-0.136)	0.141 (0.126-0.153)	0.162 (0.145-0.177)	0.180 (0.159-0.196)
<b>4-day</b>	0.036 (0.033-0.040)	0.044 (0.040-0.048)	0.055 (0.050-0.060)	0.064 (0.058-0.069)	0.076 (0.070-0.083)	0.087 (0.079-0.095)	0.098 (0.088-0.107)	0.110 (0.099-0.119)	0.127 (0.113-0.138)	0.140 (0.124-0.153)
<b>7-day</b>	0.024 (0.023-0.026)	0.029 (0.027-0.032)	0.036 (0.033-0.039)	0.042 (0.039-0.045)	0.050 (0.046-0.054)	0.057 (0.052-0.061)	0.064 (0.058-0.069)	0.071 (0.065-0.077)	0.082 (0.074-0.089)	0.091 (0.081-0.099)
<b>10-day</b>	0.019 (0.018-0.021)	0.023 (0.022-0.025)	0.028 (0.026-0.030)	0.032 (0.030-0.035)	0.038 (0.035-0.041)	0.043 (0.039-0.046)	0.047 (0.044-0.051)	0.052 (0.048-0.056)	0.059 (0.054-0.064)	0.065 (0.059-0.070)
<b>20-day</b>	0.013 (0.012-0.014)	0.016 (0.015-0.017)	0.019 (0.017-0.020)	0.021 (0.020-0.022)	0.024 (0.022-0.026)	0.027 (0.025-0.028)	0.029 (0.027-0.031)	0.032 (0.029-0.034)	0.035 (0.032-0.038)	0.038 (0.034-0.041)
<b>30-day</b>	0.011 (0.010-0.012)	0.013 (0.012-0.014)	0.015 (0.014-0.016)	0.017 (0.016-0.018)	0.019 (0.018-0.020)	0.020 (0.019-0.022)	0.022 (0.021-0.023)	0.024 (0.022-0.025)	0.026 (0.024-0.027)	0.027 (0.025-0.029)
<b>45-day</b>	0.009 (0.009-0.010)	0.011 (0.010-0.011)	0.012 (0.012-0.013)	0.014 (0.013-0.014)	0.015 (0.014-0.016)	0.016 (0.015-0.017)	0.017 (0.016-0.018)	0.018 (0.017-0.019)	0.020 (0.019-0.021)	0.021 (0.019-0.022)
<b>60-day</b>	0.008 (0.008-0.009)	0.010 (0.009-0.010)	0.011 (0.011-0.012)	0.012 (0.011-0.013)	0.013 (0.013-0.014)	0.014 (0.014-0.015)	0.015 (0.014-0.016)	0.016 (0.015-0.017)	0.017 (0.016-0.018)	0.018 (0.017-0.019)


<sup>1</sup> Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS). Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values. Please refer to NOAA Atlas 14 document for more information.

[Back to Top](#)

**PF graphical**



Average recurrence interval (years)
1
2
5
10
25
50
100
200
500
1000




Duration
5-min
10-min
15-min
30-min
60-min
2-hr
3-hr
6-hr
12-hr
24-hr
2-day
3-day
4-day
7-day
10-day
20-day
30-day
45-day
60-day

NOAA Atlas 14, Volume 2, Version 3

**Maps & aeriels**

Created (GMT): Wed Apr 6 19:44:28 2016


**Small scale terrain**



Large scale terrain



Large scale map



Large scale aerial



[Back to Top](#)

---

[US Department of Commerce](#)  
[National Oceanic and Atmospheric Administration](#)  
[National Weather Service](#)  
[National Water Center](#)  
1325 East West Highway  
Silver Spring, MD 20910

Questions?: [HDSC.Questions@noaa.gov](mailto:HDSC.Questions@noaa.gov)

[Disclaimer](#)

# Hydrograph Return Period Recap

Hydraflow Hydrographs by Intelisolve v9.1

Hyd. No.	Hydrograph type (origin)	Inflow Hyd(s)	Peak Outflow (cfs)								Hydrograph description
			1-Yr	2-Yr	3-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr	
1	Rational	-----	0.540	0.642	-----	0.751	0.827	0.918	0.977	1.037	Pre Development
2	Rational	-----	0.460	0.547	-----	0.639	0.704	0.781	0.831	0.883	Post Bypass
5	Rational	-----	0.470	0.559	-----	0.654	0.720	0.799	0.851	0.903	post to bed Lot 2
6	Reservoir	5	0.000	0.000	-----	0.000	0.000	0.000	0.000	0.000	Bed Lot 2
7	Combine	2, 6	0.460	0.547	-----	0.639	0.704	0.781	0.831	0.883	total post



# Hydrograph Summary Report

Hydraflow Hydrographs by Intelisolve v9.1

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph description	
1	Rational	0.540	1	15	486	----	-----	-----	Pre Development	
2	Rational	0.460	1	15	414	----	-----	-----	Post Bypass	
5	Rational	0.470	1	15	423	----	-----	-----	post to bed Lot 2	
6	Reservoir	0.000	1	1358	0	5	374.18	415	Bed Lot 2	
7	Combine	0.460	1	15	414	2, 6	-----	-----	total post	
Cahill.gpw					Return Period: 1 Year			Thursday, May 24, 2018		

# Hydrograph Summary Report

Hydraflow Hydrographs by Intelisolve v9.1

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph description
1	Rational	0.642	1	15	578	---	-----	-----	Pre Development
2	Rational	0.547	1	15	492	---	-----	-----	Post Bypass
5	Rational	0.559	1	15	503	---	-----	-----	post to bed Lot 2
6	Reservoir	0.000	1	1571	0	5	374.47	494	Bed Lot 2
7	Combine	0.547	1	15	492	2, 6	-----	-----	total post
Cahill.gpw					Return Period: 2 Year			Thursday, May 24, 2018	

# Hydrograph Summary Report

Hydraflow Hydrographs by Intelisolve v9.1

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph description
1	Rational	1.037	1	15	934	----	-----	-----	Pre Development
2	Rational	0.883	1	15	795	----	-----	-----	Post Bypass
5	Rational	0.903	1	15	813	----	-----	-----	post to bed Lot 2
6	Reservoir	0.000	1	2270	0	5	376.00	802	Bed Lot 2
7	Combine	0.883	1	15	795	2, 6	-----	-----	total post
Cahill.gpw					Return Period: 100 Year			Thursday, May 24, 2018	

# Hydraflow Table of Contents

<b>Hydrograph Return Period Recap .....</b>	<b>1</b>
<b>1 - Year</b>	
<b>Summary Report .....</b>	<b>2</b>
<b>Hydrograph Reports .....</b>	<b>3</b>
<b>2 - Year</b>	
<b>Summary Report .....</b>	<b>3</b>
<b>Hydrograph Reports .....</b>	<b>4</b>
<b>100 - Year</b>	
<b>Summary Report .....</b>	<b>4</b>
<b>Hydrograph Reports .....</b>	<b>5</b>

# **INFILTRATION**

# Hydrograph Return Period Recap

Hydraflow Hydrographs by Intelisolve v9.1

Hyd. No.	Hydrograph type (origin)	Inflow Hyd(s)	Peak Outflow (cfs)								Hydrograph description
			1-Yr	2-Yr	3-Yr	5-Yr	10-Yr	25-Yr	50-Yr	100-Yr	
1	SCS Runoff	-----	-----	0.476	-----	-----	-----	-----	-----	-----	bed 2
2	Reservoir	1	-----	0.000	-----	-----	-----	-----	-----	-----	Bed Lot 2

# Hydrograph Summary Report

Hydraflow Hydrographs by Intelisolve v9.1

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph description
1	SCS Runoff	0.476	2	716	968	---	-----	-----	bed 2
2	Reservoir	0.000	2	598	0	1	375.13	654	Bed Lot 2

# Hydrograph Report

Hydraflow Hydrographs by Intelisolve v9.1

Thursday, May 24, 2018


## Hyd. No. 1

bed 2

Hydrograph type = SCS Runoff  
Storm frequency = 2 yrs  
Time interval = 2 min  
Drainage area = 0.150 ac  
Basin Slope = 0.0 %  
Tc method = USER  
Total precip. = 3.27 in  
Storm duration = 24 hrs

Peak discharge = 0.476 cfs  
Time to peak = 716 min  
Hyd. volume = 968 cuft  
Curve number = 86\*  
Hydraulic length = 0 ft  
Time of conc. (Tc) = 5.00 min  
Distribution = Type II  
Shape factor = 484

\* Composite (Area/CN) =  $[(0.100 \times 98) + (0.050 \times 61)] / 0.150$





# Hydrograph Report

Hydraflow Hydrographs by Intelisolve v9.1

Thursday, May 24, 2018


## Hyd. No. 2

Bed Lot 2

Hydrograph type = Reservoir  
Storm frequency = 2 yrs  
Time interval = 2 min  
Inflow hyd. No. = 1 - bed 2  
Reservoir name = Lot 2

Peak discharge = 0.000 cfs  
Time to peak = 598 min  
Hyd. volume = 0 cuft  
Max. Elevation = 375.13 ft  
Max. Storage = 654 cuft

Storage Indication method used. Exfiltration extracted from Outflow.



# Pond Report

Hydraflow Hydrographs by Intelisolve v9.1

Thursday, May 24, 2018

## Pond No. 2 - Lot 2

### Pond Data

UG Chambers - Invert elev. = 373.00 ft, Rise x Span = 2.45 x 4.00 ft, Barrel Len = 30.00 ft, No. Barrels = 2, Slope = 0.00%, Headers = No  
 Encasement - Invert elev. = 372.50 ft, Width = 6.25 ft, Height = 4.00 ft, Voids = 40.00%

### Stage / Storage Table

Stage (ft)	Elevation (ft)	Contour area (sqft)	Incr. Storage (cuft)	Total storage (cuft)
0.00	372.50	n/a	0	0
0.40	372.90	n/a	60	60
0.80	373.30	n/a	103	163
1.20	373.70	n/a	116	279
1.60	374.10	n/a	114	393
2.00	374.50	n/a	109	502
2.40	374.90	n/a	101	603
2.80	375.30	n/a	89	692
3.20	375.70	n/a	65	757
3.60	376.10	n/a	60	817
4.00	376.50	n/a	60	877

### Culvert / Orifice Structures

	[A]	[B]	[C]	[PrfRsr]
Rise (in)	= 4.00	4.00	0.00	0.00
Span (in)	= 4.00	4.00	0.00	0.00
No. Barrels	= 1	1	0	0
Invert El. (ft)	= 376.17	376.17	0.00	0.00
Length (ft)	= 25.00	0.00	0.00	0.00
Slope (%)	= 5.00	0.00	0.00	n/a
N-Value	= .013	.013	.013	n/a
Orifice Coeff.	= 0.60	0.60	0.60	0.60
Multi-Stage	= n/a	Yes	No	No

### Weir Structures

	[A]	[B]	[C]	[D]
Crest Len (ft)	= 0.00	0.00	0.00	0.00
Crest El. (ft)	= 0.00	0.00	0.00	0.00
Weir Coeff.	= 3.33	3.33	3.33	3.33
Weir Type	= ---	---	---	---
Multi-Stage	= No	No	No	No
Exfil.(in/hr)	= 0.460 (by Wet area)			
TW Elev. (ft)	= 0.00			

Note: Culvert/Orifice outflows are analyzed under inlet (ic) and outlet (oc) control. Weir risers checked for orifice conditions (ic) and submergence (s).

### Stage / Storage / Discharge Table

Stage ft	Storage cuft	Elevation ft	Clv A cfs	Clv B cfs	Clv C cfs	PrfRsr cfs	Wr A cfs	Wr B cfs	Wr C cfs	Wr D cfs	Exfil cfs	User cfs	Total cfs
0.00	0	372.50	0.00	0.00	---	---	---	---	---	---	0.000	---	0.00
0.40	60	372.90	0.00	0.00	---	---	---	---	---	---	0.005	---	0.00
0.80	163	373.30	0.00	0.00	---	---	---	---	---	---	0.005	---	0.01
1.20	279	373.70	0.00	0.00	---	---	---	---	---	---	0.006	---	0.01
1.60	393	374.10	0.00	0.00	---	---	---	---	---	---	0.006	---	0.01
2.00	502	374.50	0.00	0.00	---	---	---	---	---	---	0.007	---	0.01
2.40	603	374.90	0.00	0.00	---	---	---	---	---	---	0.007	---	0.01
2.80	692	375.30	0.00	0.00	---	---	---	---	---	---	0.008	---	0.01
3.20	757	375.70	0.00	0.00	---	---	---	---	---	---	0.008	---	0.01
3.60	817	376.10	0.00	0.00	---	---	---	---	---	---	0.009	---	0.01
4.00	877	376.50	0.12 ic	0.12 ic	---	---	---	---	---	---	0.009	---	0.13

**ENTIRE PROJECT AREA**

**WORKSHEET 4. CHANGE IN RUNOFF VOLUME FOR 2-YR STORM EVENT**

PROJECT: Cahill Property (Post Dev)  
 Drainage Area: 0.15 acres  
 2-Year Rainfall: 3.2 in  
 Total Site Area: 0.15 acres  
 Protected Site Area: 0.00 acres  
 Managed Area: 0.00 acres

**Existing Conditions:**

Cover Type / Condition	Soil Type	Area (sf)	Area (ac)	CN	S	la 0.2*s	Q Runoff <sup>1</sup> (in)	Runoff Volume <sup>2</sup> (ft <sup>3</sup> )
Meadow		0	0.00	58	7.24	1.45	0.341	0
Woods	B	0	0.00	55	8.18	1.64	0.251	0
Impervious	B	0	0.00	98	0.20	0.04	2.967	0
Woods		0	0.00	70	4.29	0.86	0.828	0
<b>TOTAL:</b>			<b>0.00</b>					<b>0</b>

**Developed Conditions:**

Cover Type / Condition	Soil Type	Area (sf)	Area (ac)	CN	S	la 0.2*s	Q Runoff <sup>1</sup> (in)	Runoff Volume <sup>2</sup> (ft <sup>3</sup> )
Lawn	B	2,022	0.05	61	6.39	1.28	0.444	75
Woods	B	0	0.00	55	8.18	1.64	0.251	0
Impervious	B	4,367	0.10	98	0.20	0.04	2.967	1080
Lawn		0	0.00	74	3.51	0.70	1.038	0
Gravel		0	0.00	89	1.24	0.25	2.082	0
Impervious		0	0.00	98	0.20	0.04	2.967	0
<b>TOTAL:</b>			<b>0.15</b>					<b>1,155</b>

**2-Year Volume Increase (ft<sup>3</sup>): 1,155**

2-Year Volume Increase = Developed Conditions Runoff Volume - Existing Conditions Runoff Volume

1. Runoff (in) = Q = (P-0.2S)<sup>2</sup> / (P + 0.8S) where

P = 2-Year Rainfall (in)

S = (1000/CN) - 10

2. Runoff Volume (CF) = Q x Area x 1/12

Q = Runoff (in)

Area = Land Use Area (sq. ft.)

NOTE: Runoff volume must be calculated for EACH land use type/condition and HSGI. The use of a weighted CN value for volume calculations is not acceptable.

TOTAL INFILTRATION = 1,155 + 333 = 1488 C.F.



EDWARD B. WALSH & ASSOCIATES, INC.  
Complete Civil Engineering Design / Consultation Services

# RAIN GARDEN VOLUME CALCULATIONS

DATE: 5/14/2018

BY: AE

JOB NO.: 4062 PROJECT: Cahill Lot 2 RG 1 TOWNSHIP: WESTTOWN


DESCRIPTION: RAIN GARDEN

Area of Rain Garden	Depth of soil in Rain Garden	Void Area	Ponded Water	Total Volume (C.F.)	
321	1.5	0.17	419	0.6	333

Equation: Area of rain garden x depth of soil x void area + ponded water x 0.6 = Total Volume

# **CONVEYANCE**

# Hydraflow Plan View



Ballester storm 2

No. Lines: 4

05-24-2018

# Inlet Report

Line No	Inlet ID	Q = CIA (cfs)	Q carry (cfs)	Q capt (cfs)	Q byp (cfs)	Junc type	Curb Inlet		Grate Inlet			Gutter						Inlet			Byp line No					
							Ht (in)	L (ft)	area (sqft)	L (ft)	W (ft)	So (ft/ft)	W (ft)	Sw (ft/ft)	Sx (ft/ft)	n	Depth (ft)	Spread (ft)	Depth (ft)	Spread (ft)		Depth (ft)	Spread (ft)	Depr (in)		
1		0.00	1.67	0.00	1.67	MH	6.0	6.00	2.00	4.00	2.00	Sag	2.00	0.080	0.050	0.013	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	2.00	Off
2		0.00	1.67	0.00	1.67	MH	6.0	6.00	2.00	4.00	2.00	Sag	2.00	0.080	0.050	0.013	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	2.00	1
3		1.67*	0.00	0.00	1.67	MH	6.0	6.00	2.00	4.00	2.00	Sag	2.00	0.080	0.050	0.013	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	2.00	2
4		6.04*	0.00	6.04	0.00	DrGrt	6.0	6.00	2.00	4.00	2.00	Sag	2.00	0.080	0.050	0.013	0.40	17.94	17.94	0.40	17.94	0.40	17.94	2.00	3	
<b>Ballester storm 2</b>												Number of lines: 4						Run Date: 05-24-2018								

NOTES: Inlet N-Values = 0.013 ; Intensity = 161.33 / (Inlet time + 21.80) ^ 0.91; Return period = 100 Yrs. ; \* Indicates Known Q added

# Storm Sewer Summary Report

Line No.	Line ID	Flow rate (cfs)	Line size (in)	Line length (ft)	Invert EL Dn (ft)	Invert EL Up (ft)	Line slope (%)	HGL down (ft)	HGL up (ft)	Minor loss (ft)	HGL Junct (ft)	Dns line No.
1	outfall to mh1b	7.71	24 c	30.0	364.50	364.80	1.000	365.48	365.78	n/a	365.78	End
2	mh1b to mh1a	7.71	24 c	66.0	365.00	370.74	8.697	366.08	371.72	n/a	371.72	1
3	mh1a to mh1	7.71	24 c	30.0	370.94	372.79	6.167	372.02	373.77	n/a	373.77	2
4	m1 1 to inlet 1	6.04	24 c	36.0	372.99	375.13	5.944	374.11	376.00	n/a	376.00	3

Ballester storm 2

Number of lines: 4

Run Date: 05-24-2018

NOTES: c = cir; e = ellip; b = box; Return period = 100 Yrs. ; ] - Line contains hyd. jump.




# FL-DOT Report

Line No	To Line	Type of struc	n - value	Len (ft)	Drainage Area			Time of conc (min)	Time of flow in sect (min)	Inten (l) (in/hr)	Total CA	Add Q Total flow (cfs)	Inlet elev (ft)	Elev of HGL			Rise Span	HGL Pipe	Actual		Date: 05-24-2018						
					Incr- ment (ac)	Sub- total (ac)	Sum CA							Up (ft)	Down (ft)	Fall (ft)			Size (in)	Slope (%)		Vel (ft/s)	Cap (cfs)	Frequency: 100 yrs			
																									Elev of Invert		
																									Line description		
1	End	MH	0.013	30.0	0.00	0.00	0.00	0.96	0.20	0.0	0.00	369.50	365.78	366.80	364.80	0.30	24	1.00	5.01	7.71	05-24-2018						
					0.00	0.00	0.00				7.71		366.50	367.00	364.50	0.30	24	1.00	7.20	22.62							
					0.00	0.00	0.00						364.80	365.00	364.50	0.30	Cir										
2	1	MH	0.013	66.0	0.00	0.00	0.00	0.52	0.45	0.0	0.00	378.25	371.72	366.08	5.64	24	8.55	4.73	7.71	05-24-2018							
					0.00	0.00	0.00				7.71		372.74	367.00	367.00	5.74	24	8.70	21.23	66.70							
					0.00	0.00	0.00						370.74	365.00	365.00	5.74	Cir										
3	2	MH	0.013	30.0	0.00	0.00	0.00	0.31	0.20	0.0	0.00	380.04	373.77	372.02	1.75	24	5.84	4.73	7.71	05-24-2018							
					0.00	0.00	0.00				7.71		374.79	372.94	372.94	1.85	24	6.17	17.88	56.17							
					0.00	0.00	0.00						372.79	370.94	370.94	1.85	Cir										
4	3	DrGrt	0.013	36.0	0.00	0.00	0.00	0.00	0.31	0.0	0.00	379.50	376.00	374.11	1.89	24	5.26	3.98	6.04	05-24-2018							
					0.00	0.00	0.00				6.04		377.13	374.99	374.99	2.14	24	5.94	17.55	55.15							
					0.00	0.00	0.00						375.13	372.99	372.99	2.14	Cir										

NOTES: Intensity = 161.33 / (Inlet time + 21.80) ^ 0.91 (in/hr) ; Time of flow in section is based on full flow.

Ballester storm 2

# Storm Sewer Profile



# **INFILTRATION TESTING**

---

# **SOILS REPORT FOR STORMWATER RECHARGE SUITABILITY**

---

## **9 Jacqueline Drive**

**WESTTOWN TOWNSHIP  
CHESTER COUNTY**

March 9, 2018

Prepared By:



Edward B. Walsh and Associates, Inc.  
125 Dowlin Forge Road, Lionville Professional Center  
Exton, PA 19341-1550  
610-903-0060

## **Project Background**

Edward B. Walsh and Associates, Inc. (EBW) conducted a soils evaluation to determine the potential for storm water infiltration on proposed Lot #2 located at 9 Jacqueline Drive in Westtown Township, Chester County, Pa.

## **Soils and Geology**

According to Soil Survey Staff, Natural Resource Conservation Service, United States Department of Agriculture Web Soil Survey; available at <http://websoilsurvey.nrcs.usda.gov> the property is mapped as containing Gladstone (GdC) and Urban Land Gladstone Complex (UrID) soil series, Figure #1.

The Gladstone series consists of very deep, well drained soils formed in residuum and colluvium from granitic gneiss. The depth to a water table is generally greater than eighty (80) inches and the depth to bedrock is generally between sixty-five (65) and sixty-seven (67) inches below the ground surface.

## **Methods**

One (1) soil probe was conducted near the northwest corner of Lot #2, see attached map for approximate location. One (1) soil probe was conducted in the northwest corner of lot #2. The soil probe was excavated by a backhoe to allow for the collection of detailed soil morphology data, included in Appendix A. The objective of the soil evaluations was to determine if the soil conditions to a depth of a minimum of two (2) feet below the proposed infiltration area were conducive to groundwater recharge. Particular soil conditions that are not conducive to storm water infiltration are bedrock, groundwater or seasonally high water table and karst areas.

## **Results**

Test pit (TP#1) was excavated within the area of the proposed storm water recharge bed. The test pit was excavated to a depth of 9 feet below grade. No limiting zones were identified in the test pit. Soil infiltration testing was conducted at various depths (5 feet and 7 feet below grade) to account for the change in depth below existing grade across the proposed bed. The average infiltration rate was calculated to be 0.79 inches per hour (not including the PA DEP required safety factor of 2).

## **Summary**

The results of the soils evaluations indicate that site as tested is generally suitable for storm water infiltration in locations and depths referenced in this report.

EDWARD B. WALSH AND ASSOCIATES, INC



Scott Andress, SEO  
Environmental Scientist


# Figure 1

Soil Map—Chester County, Pennsylvania



Soil Map may not be valid at this scale.

Map Scale: 1:760 if printed on A portrait (8.5" x 11") sheet.



## MAP LEGEND

- Area of Interest (AOI)
  - Area of Interest (AOI)
- Soils
  - Soil Map Unit Polygons
  - Soil Map Unit Lines
  - Soil Map Unit Points
- Special Point Features
  - Blowout
  - Borrow Pit
  - Clay Spot
  - Closed Depression
  - Gravel Pit
  - Gravelly Spot
  - Landfill
  - Lava Flow
  - Marsh or swamp
  - Mine or Quarry
  - Miscellaneous Water
  - Perennial Water
  - Rock Outcrop
  - Saline Spot
  - Sandy Spot
  - Severely Eroded Spot
  - Sinkhole
  - Slide or Slip
  - Sodic Spot
- Water Features
  - Streams and Canals
- Transportation
  - Rails
  - Interstate Highways
  - US Routes
  - Major Roads
  - Local Roads
- Background
  - Aerial Photography
- Spoil Area
- Stony Spot
- Very Stony Spot
- Wet Spot
- Other
- Special Line Features

## MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service  
 Web Soil Survey URL:  
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Chester County, Pennsylvania  
 Survey Area Data: Version 9, Oct 3, 2017

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Jul 25, 2014—Aug 11, 2014

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.



## Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
GdC	Gladstone gravelly loam, 8 to 15 percent slopes	0.6	47.5%
UrID	Urban land-Gladstone complex, 8 to 25 percent slopes	0.7	52.5%
<b>Totals for Area of Interest</b>		<b>1.3</b>	<b>100.0%</b>

# Appendix A

# SOIL PROFILE

<b>Date:</b> 3/16/2018		<b>Location:</b> 9 Jacqueline Drive				<b>Person Conducting Test:</b> S. Andress			<b>Probe #</b> 1	
HORIZON	DEPTH	TEXTURE	R4/3	STRUCTURE	CONSISTENCE	% COARSE FRAG.	Redoximorphic Features	Additional Information		
Ap	0-8	Silt Loam	10YR4/4	M. Gran.	Friable	-----	-----			
Bt1	8-12	Silt Loam	7.5YR5/4	M. SBK	Friable	-----	-----			
Bt2	12-30	Silt Loam	7.5YR5/6	M. SBK	Friable	-----	-----			
C	30-108	Loam	Variegated	Structureless	Firm in Place - Friable	20	-----			

**Limiting Zone Type and Depth:** 108" Bottom of Probe      **Slope %** 3-8      **Loading Rate:** NA

<b>Date:</b>		<b>Location:</b>				<b>Person Conducting Test:</b>			<b>Probe #</b>	
HORIZON	DEPTH	TEXTURE	COLOR	STRUCTURE	CONSISTENCE	% COARSE FRAG.	Redoximorphic Features	Additional Information		

**Limiting Zone Type and Depth:**      **Slope %**      **Loading Rate:**

# Appendix B

## Cased Borehole Falling Head Permeability Testing

**Location:** 9 Jacqueline Drive

**Test ID:** TP#1 / I#1

**Person Conducting Test:** S. Andress

**Date of Test:** 3/16/2018

**Test Information:**

Overall Casing Length (inches): 12.00

Casing Diameter (in.): 4.00

Depth Below Ex. Grade (ft.): 5.00

Holes are presoaked 1 hour prior to conducting readings

Time (min.)	Water Level Drop (inches)
0.0	NA
30.0	5.00
60.0	4.75
90.0	4.25
120.0	4.25
150.0	4.00
180.0	4.00

Coefficient of Permeability (K) =  $[A/F \cdot D \cdot t] \times \ln(h_1/h_2)$

where: K = Vertical Permeability (cm/sec)

A = Cross sectional Area of Cased Hole 12.56

F = Shape Factor (2.75 for flat bottom) 2.75

D = Cased Hole Diameter 4.00

t = Time for head to change from h1 to h2 30.00

h1 = Initial height of water column in casing 12.00

h2 = Final height of water column in casing 8.00

**K = 0.0154322478 in/min**

**K = 0.926 in/hour**

## Cased Borehole Falling Head Permeability Testing

**Location:** 9 Jacqueline Drive

**Test ID:** TP#1 / I#2

**Person Conducting Test:** S. Andress

**Date of Test:** 3/16/2018

**Test Information:**

Overall Casing Length (inches): 12.00

Casing Diameter (in.): 4.00

Depth Below Ex. Grade (ft.): 7.00

Holes are presoaked 1 hour prior to conducting readings

Time (min.)	Water Level Drop (inches)
0.0	NA
30.0	3.75
60.0	3.50
90.0	3.25
120.0	3.25
150.0	3.25
180.0	3.00

Coefficient of Permeability (K) =  $[A/F \cdot D \cdot t] \times \ln(h_1/h_2)$

where: K = Vertical Permeability (cm/sec)

A = Cross sectional Area of Cased Hole 12.56

F = Shape Factor (2.75 for flat bottom) 2.75

D = Cased Hole Diameter 4.00


t = Time for head to change from h1 to h2 30.00

h1 = Initial height of water column in casing 12.00


h2 = Final height of water column in casing 9.00

**K = 0.0109493540 in/min**

**K = 0.657 in/hour**



LOCATION MAP  
SCALE: 1"=2000'



EXISTING IMPERVIOUS COVERAGE: LOT 1  
HOUSE & ROOF OVERHANG: 3,241 SF  
DRIVE: 122 SF  
WALKS & PATIOS: 615 SF  
TOTAL: 3,978 SF

ZONING DATA  
R-2 RESIDENTIAL DISTRICT W/PUBLIC SEWER AND WATER

	LOT 1	LOT 2
MIN. LOT AREA	22,000 S.F.	22,000 S.F.
MIN. LOT WIDTH	100'	100'
● BLDG. LINE	100'	100'
● STREET LINE	50'	50'
MIN. SIDE YARD	10' (25' AGG)	10', 15'
MIN. FRONT YARD	40'	40'
MIN. REAR YARD	30'	30'
MAX. LOT COVERAGE	25%	25%
MAX. BLDG. HEIGHT	35'	35'
TOTAL TRACT AREA	= 1,111 AC.	
NO. LOT PROPOSED	= 2	

WAIVER REQUEST: SECTION 149-600 TO ALLOW THE PLAN TO BE CONSIDERED PRELIMINARY & FINAL.

COMMONWEALTH OF PENNSYLVANIA COUNTY OF CHESTER  
On this \_\_\_\_\_ day of \_\_\_\_\_ A.D. 2018 before me, the subscriber, a Notary Public of the Commonwealth of Pennsylvania, residing in \_\_\_\_\_ personally appeared Adam R. Loew, who acknowledges himself to be the President of Southdown Properties Inc. the general Partner of Westtown Woods, L.P. and that as such President, being authorized to do so, he executed the foregoing plan by signing that the said partnership is the owner of the designated land, that all necessary approval of the plan has been obtained and is endorsed thereon, and that the said partnership desires that the foregoing plan may be duly recorded.  
Adam R. Loew  
Notary Public  
My Commission Expires: \_\_\_\_\_

COMMONWEALTH OF PENNSYLVANIA COUNTY OF CHESTER  
On the \_\_\_\_\_ day of \_\_\_\_\_ A.D. 20\_\_\_\_ before me, the subscriber, a Notary Public of the Commonwealth of Pennsylvania, residing in \_\_\_\_\_ who personally appeared \_\_\_\_\_ who acknowledges himself to be the \_\_\_\_\_ and that as such to do so, he executed the foregoing plan by signing his name by himself as \_\_\_\_\_ that he is the owner of the designated land, that necessary approval of the plan has been obtained and is endorsed thereon and that he desires that the foregoing plan may be duly recorded.  
Notary Public  
My Commission Expires: \_\_\_\_\_

APPROVED by the Board of Supervisors of Westtown Township, Chester County, Pa., this \_\_\_\_\_ day of \_\_\_\_\_, 2018.  
Chairperson \_\_\_\_\_ Member \_\_\_\_\_  
Vice-Chairperson \_\_\_\_\_ Member \_\_\_\_\_  
Member \_\_\_\_\_ Member \_\_\_\_\_  
Member \_\_\_\_\_  
REVIEWED by the Planning Commission of Westtown Township, Chester County, Pa., this \_\_\_\_\_ day of \_\_\_\_\_, 2018.  
Chairperson \_\_\_\_\_ Supervisor \_\_\_\_\_  
Vice-Chairperson \_\_\_\_\_ Supervisor \_\_\_\_\_  
Supervisor \_\_\_\_\_  
REVIEWED by the Chester County Planning Commission this \_\_\_\_\_ day of \_\_\_\_\_, 2018.  
Secretary \_\_\_\_\_  
REVIEWED by the Westtown Township Engineer;  
\_\_\_\_\_  
Date \_\_\_\_\_  
Recorded in the Office of the Recorder of Deeds of Chester County at West Chester, Pennsylvania in Plan book \_\_\_\_\_, Page \_\_\_\_\_, on the \_\_\_\_\_ day of \_\_\_\_\_, 2018.  
\_\_\_\_\_  
(Deputy) Recorder of Deeds

- GENERAL NOTES:
- THE PURPOSE OF THIS PLAN IS TWO FOLD:  
1) SINCE A TITLE OVERLAP WAS FOUND ALONG THE LINE COMMON TO CAHILL AND LOT 1 OF THE WESTTOWN WOODS SUBDIVISION ACCORDING TO SURVEYS PERFORMED BY ABACUS SURVEYING AND COMMONWEALTH ENGINEERS, INC., WESTTOWN WOODS, LP DESIRES TO QUITCLAIM TITLE TO THEIR PORTION OF THE OVERLAP AS SHOWN HEREON. THE QUITCLAIM AREA IS TO BECOME A PART OF THE LANDS OWNED BY JAMES P. & LINDA A. CAHILL.  
2) THE LANDS OF JAMES P. & LINDA A. CAHILL ARE TO BE SUBDIVIDED INTO 2 LOTS AS SHOWN HEREON.
  - BOUNDARY INFORMATION IS FROM A "SURVEY REPORT PLAN FOR JAMES CAHILL, 90 JACQUELINE DRIVE, WEST CHESTER, PA 19382", PREPARED BY ABACUS SURVEYING, HONEY BROOK, PA, DATED APRIL 05, 2018.
  - EXISTING FEATURES AND TOPOGRAPHIC FEATURES INFORMATION SHOWN HEREON ARE FROM A FIELD SURVEY PERFORMED BY EDWARD B. WALSH & ASSOCIATES ON MARCH 13, 2018.
  - RECORD OWNERS OF UPI 67-4F-73; LINDA A. & JAMES P. CAHILL 9 JACQUELINE DRIVE WEST CHESTER, PA. 19382
  - DEED REFERENCE: DEED BOOK 4416, PAGE 1212 BEING LOT 5 SHOW ON THE RECORD PLAN RECORDED AT THE CHESTER COUNTY RECORDER OF DEEDS IN PLAN BOOK 13, PAGE 14 .
  - EQUITABLE OWNER/ APPLICANT: WESTTOWN WOODS, L.P. 55 COUNTRY CLUB DRIVE SUITE 204 DOWNTOWN, PA 19335
  - ALL LOTS WILL BE SERVED BY PUBLIC SEWER AND WATER.
  - A STATEMENT SIGNED AND SEALED BY A REGISTERED ARCHITECT OR ENGINEER, EXPLAINING THE BUILDING METHODS TO BE USED TO OVERCOME FOUNDATION AND OTHER STRUCTURAL PROBLEMS CREATED BY SLOPE CONDITIONS, PRESERVING THE NATURAL WATERSHED, AND PREVENTING SOIL EROSION AND EXCESSIVE SURFACE WATER RUNOFF TO NEIGHBORING PROPERTIES AND/OR STREETS SHALL BE SUBMITTED FOR REVIEW TO THE TOWNSHIP ENGINEER WITH THE BUILDING PERMIT APPLICATION.
  - ALL MATERIALS ENTERING INTO THE CONSTRUCTION OF CURBS AND THE METHOD OF CONSTRUCTION AND INSTALLATION SHALL BE IN ACCORDANCE WITH PENNDOT SPECIFICATION PUBLICATION 408.
  - LOT 2 WILL BECOME PART OF THE HOMEOWNERS ASSOCIATION FOR WESTTOWN WOODS.
  - ALL STORMWATER FACILITIES OUTSIDE OF THE R.O.W. SHALL BE OWNED AND MAINTAINED BY THE HOMEOWNERS ASSOCIATION.


- REFERENCE PLANS:
- "PRELIMINARY SUBDIVISION AND LAND DEVELOPMENT PLAN FOR WESTTOWN WOODS", PREPARED BY COMMONWEALTH ENGINEERS, INC., DOWNTOWN, PA, DATED JULY 02, 2014, SHEET 2
  - "MAP OF WESTTOWN NORTH, PROPERTY OF ALBERT P. MANDES, INC." PREPARED BY YERKES ENGINEERING CO., BRYN MAWR, PA, DATED JANUARY 19, 1962, REVISED FEBRUARY 27, 1962, RECORDED IN PLAN BOOK13, PAGE 14 AT THE CHESTER COUNTY RECORDER OF DEEDS.
  - "SURVEY REPORT PLAN FOR JAMES CAHILL, 90 JACQUELINE DRIVE, WEST CHESTER, PA 19382", PREPARED BY ABACUS SURVEYING, HONEY BROOK, PA, DATED APRIL 05, 2018.

ACT 287 SERIAL NUMBER 20180862796  
Edward B. Walsh & Associates, Inc. does not guarantee the accuracy of the locations for existing subsurface utility lines, structures, etc. shown on the plans, nor does E. B. Walsh & Assoc., Inc. guarantee that all subsurface utility lines, structures, etc. are shown.  
Contractor shall verify the location and elevations of all subsurface utility lines, structures, etc. before the start of work, by calling the Pennsylvania One Call System at 1-800-242-1776.

UTILITIES NOTIFIED  
VERIZON PENNSYLVANIA, INC.  
AQUA PENNSYLVANIA, INC.  
COMCAST CABLE COMMUNICATIONS, INC.  
WESTTOWN TOWNSHIP  
PECO ENERGY




UPI 67-4F-73

JACQUELINE DRIVE




SUBDIVISION PLAN

1 7-26-18 REV. PER McCORMICK TAY LOR REVIEW OF JULY 11, 2018  
PLAN OF SUBDIVISION AND LOT LINE ADJUSTMENT FOR  
WESTTOWN WOODS, LP & JAMES P. & LINDA A. CAHILL  
WESTTOWN TOWNSHIP CHESTER COUNTY, PA.  
Edward B. Walsh & Associates, Inc. Project- 4062  
CIVIL ENGINEERS & LAND SURVEYORS Date- 5-10-18  
LIONVILLE PROFESSIONAL CENTER Scale- 1"= 30'  
125 Dowlin Forge Rd. Drawn- RBL  
Eston, Pennsylvania 19341 Checked- AE  
Phone: 610-903-0060 Sheet- 1 OF 8  
Fax: 610-903-0080  
Plotted: 7/26/2018 P:\J\4062\4062-B5 Cahill sub.pro



LOCATION MAP  
SCALE: 1"=2000'



- GENERAL NOTES:
- THE PURPOSE OF THIS PLAN IS TWO FOLD:
    - SINCE A TITLE OVERLAP WAS FOUND ALONG THE LINE COMMON TO CAHILL AND LOT 1 OF THE WESTTOWN WOODS SUBDIVISION ACCORDING TO SURVEYS PERFORMED BY ABACUS SURVEYING AND COMMONWEALTH ENGINEERS, INC., WESTTOWN WOODS, LP DESIRES TO QUITCLAIM TITLE TO THEIR PORTION OF THE OVERLAP AS SHOWN HEREON. THE QUITCLAIM AREA IS TO BECOME A PART OF THE LANDS OWNED BY JAMES P. & LINDA A. CAHILL.
    - THE LANDS OF JAMES P. & LINDA A. CAHILL ARE TO BE SUBDIVIDED INTO 2 LOTS AS SHOWN HEREON.
  - BOUNDARY INFORMATION IS FROM A "SURVEY REPORT PLAN FOR JAMES CAHILL, 90 JACQUELINE DRIVE, WEST CHESTER, PA 19382", PREPARED BY ABACUS SURVEYING, HONEY BROOK, PA, DATED APRIL 05, 2018.
  - EXISTING FEATURES AND TOPOGRAPHIC FEATURES INFORMATION SHOWN HEREON ARE FROM A FIELD SURVEY PERFORMED BY EDWARD B. WALSH & ASSOCIATES ON MARCH 13, 2018.
  - RECORD OWNERS OF UPI 67-4F-73: LINDA A. & JAMES P. CAHILL, 9 JACQUELINE DRIVE, WEST CHESTER, PA. 19382
  - DEED REFERENCE: DEED BOOK 4416, PAGE 1212 BEING LOT 5 SHOW ON THE RECORD PLAN RECORDED AT THE CHESTER COUNTY RECORDER OF DEEDS IN PLAN BOOK 13, PAGE 14.
  - EQUITABLE OWNER/ APPLICANT: WESTTOWN WOODS, LP, 55 COUNTRY CLUB DRIVE, SUITE 204 DOWNTOWN, PA 19335
  - ALL LOTS WILL BE SERVED BY PUBLIC SEWER AND WATER.
  - A STATEMENT SIGNED AND SEALED BY A REGISTERED ARCHITECT OR ENGINEER, EXPLAINING THE BUILDING METHODS TO BE USED TO OVERCOME FOUNDATION AND OTHER STRUCTURAL PROBLEMS CREATED BY SLOPE CONDITIONS, PRESERVING THE NATURAL WATERSHED, AND PREVENTING SOIL EROSION AND EXCESSIVE SURFACE WATER RUNOFF TO NEIGHBORING PROPERTIES AND/OR STREETS SHALL BE SUBMITTED FOR REVIEW TO THE TOWNSHIP ENGINEER WITH THE BUILDING PERMIT APPLICATION.
  - ALL MATERIALS ENTERING INTO THE CONSTRUCTION OF CURBS AND THE METHOD OF CONSTRUCTION AND INSTALLATION SHALL BE IN ACCORDANCE WITH PENNDOT SPECIFICATION PUBLICATION 408.
  - LOT 2 WILL BECOME PART OF THE HOMEOWNERS ASSOCIATION FOR WESTTOWN WOODS.
  - ALL STORMWATER FACILITIES OUTSIDE OF THE R.O.W. SHALL BE OWNED AND MAINTAINED BY THE HOMEOWNERS ASSOCIATION.

# JACQUELINE DRIVE


ACT 287 SERIAL NUMBER 20180862796  
 Edward B. Walsh & Associates, Inc. does not guarantee the accuracy of the locations for existing subsurface utility lines, structures, etc., shown on the plans, nor does E. B. Walsh & Assoc., Inc. guarantee that all subsurface utility lines, structures, etc. are shown.

Contractor shall verify the location and elevations of all subsurface utility lines, structures, etc. before the start of work, by calling the Pennsylvania One Call System at 1-800-242-1776.

UTILITIES NOTIFIED

VERIZON PENNSYLVANIA, INC.  
 AQUA PENNSYLVANIA, INC.  
 COMCAST CABLE COMMUNICATIONS, INC.  
 WESTTOWN TOWNSHIP  
 PECO ENERGY

UPI 67-4F-73



## CONSERVATION GRADING & UTILITIES PLAN

1 7-26-18 REV. PER McCORMICK TAYLOR REVIEW OF JULY 11, 2018

PLAN OF SUBDIVISION  
OF  
UPI 67-4F-73

WESTTOWN TOWNSHIP CHESTER COUNTY, PA.



Edward B. Walsh & Associates, Inc.  
 CIVIL ENGINEERS & LAND SURVEYORS  
 LIONVILLE PROFESSIONAL CENTER  
 125 Dowlin Forge Rd.  
 Exton, Pennsylvania 19341  
 Phone: 610-903-0060  
 Fax: 610-903-0080




Project- 4062  
 Date- 5-07-18  
 Scale- 1"= 30'  
 Drawn- RBL  
 Checked- AE  
 Sheet- 3 OF 8

Plotted: 7/26/2018 File: F:\JB\4062\4062-B5 Cahill sub.plo





LOCATION MAP  
SCALE: 1"=2000'



JACQUELINE DRIVE


LEGEND	
	EXISTING INDEX CONTOUR
	EXISTING INTERIOR CONTOUR
	PROPOSED CONTOUR
	PROPOSED SPOT ELEVATION
	PROPOSED INLET
	PROPOSED STORM SEWER PIPE
	PROPOSED WATER LINE
	EXISTING WATER LINE
	PROPOSED PRESSURE SEWER
	SOILS LINE
	EXISTING TREE LINE
	EXISTING WETLANDS
	EDGE OF PAVING
	RIGHT OF WAY LINE
	NATURALLY OCCURRING PRECAUTIONARY SLOPES
	EXISTING TREE
	PROPOSED CURB
	FENCE
	PROPOSED WALL
	PROPOSED LOT NUMBER

- GENERAL NOTES:
- THE PURPOSE OF THIS PLAN IS TWO FOLD:
    - SINCE A TITLE OVERLAP WAS FOUND ALONG THE LINE COMMON TO CAHILL AND LOT 1 OF THE WESTTOWN WOODS SUBDIVISION ACCORDING TO SURVEYS PERFORMED BY ABACUS SURVEYING AND COMMONWEALTH ENGINEERS, INC., WESTTOWN WOODS, LP DESIRES TO QUITCLAIM TITLE TO THEIR PORTION OF THE OVERLAP AS SHOWN HEREON. THE QUITCLAIM AREA IS TO BECOME A PART OF THE LANDS OWNED BY JAMES P. & LINDA A. CAHILL.
    - THE LANDS OF JAMES P. & LINDA A. CAHILL ARE TO BE SUBDIVIDED INTO 2 LOTS AS SHOWN HEREON.
  - BOUNDARY INFORMATION IS FROM A "SURVEY REPORT PLAN FOR JAMES CAHILL, 90 JACQUELINE DRIVE, WEST CHESTER, PA 19382", PREPARED BY ABACUS SURVEYING, HONEY BROOK, PA, DATED APRIL 05, 2018.
  - EXISTING FEATURES AND TOPOGRAPHIC FEATURES INFORMATION SHOWN HEREON ARE FROM A FIELD SURVEY PERFORMED BY EDWARD B. WALSH & ASSOCIATES ON MARCH 13, 2018.
  - RECORD OWNERS OF UPI 67-4F-73: LINDA A. & JAMES P. CAHILL, 9 JACQUELINE DRIVE, WEST CHESTER, PA. 19382
  - DEED REFERENCE: DEED BOOK 4416, PAGE 1212 BEING LOT 5 SHOW ON THE RECORD PLAN RECORDED AT THE CHESTER COUNTY RECORDER OF DEEDS IN PLAN BOOK 13, PAGE 14.
  - EQUITABLE OWNER/ APPLICANT: WESTTOWN WOODS, LP, 55 COUNTRY CLUB DRIVE, SUITE 204 DOWNTOWN, PA 19335
  - ALL LOTS WILL BE SERVED BY PUBLIC SEWER AND WATER.
  - A STATEMENT SIGNED AND SEALED BY A REGISTERED ARCHITECT OR ENGINEER, EXPLAINING THE BUILDING METHODS TO BE USED TO OVERCOME FOUNDATION AND OTHER STRUCTURAL PROBLEMS CREATED BY SLOPE CONDITIONS, PRESERVING THE NATURAL WATERSHED, AND PREVENTING SOIL EROSION AND EXCESSIVE SURFACE WATER RUNOFF TO NEIGHBORING PROPERTIES AND/OR STREETS SHALL BE SUBMITTED FOR REVIEW TO THE TOWNSHIP ENGINEER WITH THE BUILDING PERMIT APPLICATION.
  - ALL MATERIALS ENTERING INTO THE CONSTRUCTION OF CURBS AND THE METHOD OF CONSTRUCTION AND INSTALLATION SHALL BE IN ACCORDANCE WITH PENNDOT SPECIFICATION PUBLICATION 408.
  - LOT 2 WILL BECOME PART OF THE HOMEOWNERS ASSOCIATION FOR WESTTOWN WOODS.
  - ALL STORMWATER FACILITIES OUTSIDE OF THE R.O.W. SHALL BE OWNED AND MAINTAINED BY THE HOMEOWNERS ASSOCIATION.

ACT 287 SERIAL NUMBER 20180862796  
Edward B. Walsh & Associates, Inc. does not guarantee the accuracy of the locations for existing subsurface utility lines, structures, etc., shown on the plans, nor does E. B. Walsh & Assoc., Inc. guarantee that all subsurface utility lines, structures, etc. are shown.  
Contractor shall verify the location and elevations of all subsurface utility lines, structures, etc. before the start of work, by calling the Pennsylvania One Call System at 1-800-242-1776.

UTILITIES NOTIFIED  
VERIZON PENNSYLVANIA, INC.  
AQUA PENNSYLVANIA, INC.  
COMCAST CABLE COMMUNICATIONS, INC.  
WESTTOWN TOWNSHIP  
PECO ENERGY

UPI 67-4F-73



CONSERVATION  
GRADING & UTILITIES PLAN

1 7-26-18 REV. PER McCORMICK TAYLOR REVIEW OF JULY 11, 2018









PLAN OF SUBDIVISION  
OF  
UPI 67-4F-73

WESTTOWN TOWNSHIP CHESTER COUNTY, PA.  
Edward B. Walsh & Associates, Inc.  
CIVIL ENGINEERS & LAND SURVEYORS  
LIONVILLE PROFESSIONAL CENTER  
125 Dowlin Forge Rd.  
Eaton, Pennsylvania 19341  
Phone: 610-903-0060  
Fax: 610-903-0080

Project- 4062  
Date- 5-07-18  
Scale- 1"= 30'  
Drawn- RBL  
Checked- AE  
Sheet- 3 OF 8

Plotted: 7/26/2018 File: F:\JB\4062\4062-B5 Cahill sub.plo





**SEED MIX SPECIFICATIONS**

Grass Seed: All seed shall be fresh, and new crop seed shall be labeled in accordance with the U.S. Department of Agriculture's Rules and Regulations under the Federal Seed Act in effect on the date of invitation for bids. All seed shall be furnished in sealed standard containers, bearing the warranty of the supplier and certifying as to the kind, percent by weight, purity and germination. The grass seed shall contain the percentages of varieties and shall be of the quality indicated by the percentages of purity and germination indicated on the list furnished with the applicable plan. Seed mix shall be as specified. Spread at the rate of 4 lbs. per 1000 sq. ft. minimum for slopes 3:1 if greater, use 5 lbs. per 1000 sq. feet.

**PERMANENT SEEDING DATES MARCH 1 TO JUNE 1, AUGUST 1 TO OCTOBER 1**

GRASS SEED	PARTS BY WEIGHT	%PURITY	GERMINATION
NAME			
Kentucky Blue Grass	35%	95%	85%
Varieties			
Perennial Ryegrass	35%	95%	80%
Perennial Ryegrass	15%	95%	85%
Annual Ryegrass	15%	90%	80%

Mulch: Shall be hay which is free of weeds and seeds, not moldy or rotten, and shall be applied at all disturbed areas at a rate of 3 tons per acre.

Kentucky Bluegrass Sod (if called for)  
Sod shall be grown under supervision of the Bureau of Plant Industry Pennsylvania Department of Agriculture or shall be composed of only Blue Tag Certified Seed.

Temporary Seeding Dates: Anytime

Temporary Seeding: Shall be annual ryegrass at 40 lbs. per acre. Site preparation - apply 1 ton of agricultural grade limestone per acre plus fertilizer at the rate of 50-50-50 per acre and work in where possible. After seeding, mulch with hay or straw at a rate of 3 tons per acre.

Hydroseeding: Shall be lime, fertilizer, grass seeds, legume seeds and inculant mixed with water and applied as slurry, at a rate of 1,000 gallons per acre. Fertilizer: at rate of 50-100-100 per acre. Inculant: use 5 times rate recommended on the package when seeding with a hydroseeder.

**PERMANENT SEEDING:**  
For permanent seeding, soil supplements shall be applied to areas to be seeded as follows: 10-20-20 fertilizer shall be applied to 25 LBS/1000 Sq. Ft. pulverized dolomite limestone at 90 LBS/1000 Sq. Ft.

# EROSION & SEDIMENTATION CONTROL DETAILS

1 7-26-18 REV. PER McCORMICK TAYLOR REVIEW OF JULY 11, 2018

PLAN OF SUBDIVISION  
FOR  
**PARCEL 67 -4F -73**



WESTTOWN TOWNSHIP CHESTER COUNTY, PA.

Edward B. Walsh & Associates, Inc.  
CIVIL ENGINEERS & SURVEYORS  
LIONVILLE PROFESSIONAL CENTER  
125 Dowlin Forge Rd.  
Eaton, Pennsylvania 19341  
Phone: 610-903-0060  
Fax: 610-903-0080

**Project- 4062**  
**Date- 2/21/18**  
**Scale- N.T.S.**  
**Drawn-**  
**Checked- AE**  
**Sheet- 5 OF 8**

**EBW**

Plotted: 7/26/2018 File: F:\JB\4062\4062-B5 Cahill sub.plo




JACQUELINE DRIVE

SOILS SERIES AND MAP SYMBOL	DEPTH TO-		PERMEABILITY (MICROMETER/HR.)	AVAILABLE MOISTURE CAPACITY (IN. PER IN. OF SOIL DEPTH)	REACTION PH	SUITABILITY AS SOURCE OF	
	SEASONAL HIGH WATER TABLE (FT.)	BEDROCK (FT.)				TOPSOIL	ROAD FILL
Gladstone GdB GdC	5+	5+	9.17 22.30	.14 .14	6.3 6.1	Fair	Fair


SOILS CLASSIFICATION	
GdC	GLADSTONE GRAVELLY LOAM, 8 TO 15 PERCENT SLOPES
UrLD	URBAN LAND-GLADSTONE COMPLEX, 5 TO 25 PERCENT SLOPES

**SOIL NOTE**

- The site contains mapped Worham Soils that have been tested and found not to be present to the extent mapped. The Worham Soils are limited to the shaded area depicted on the plan.
- If any wet or unsuitable soils are encountered through the course of construction, they shall not be used to construct roadways, basin berms or other structural fill.



LOCATION MAP  
SCALE: 1"=2000'



**ENGINEERS CERTIFICATION**

I, THEODORE GACOMIS, P.E., ON THIS DATE 5/7/2018, HEREBY CERTIFY THAT THE STORMWATER MANAGEMENT DESIGN AND SYSTEM AS PROVIDED MEETS ALL DESIGN STANDARDS AND CRITERIA OF WESTTOWN TOWNSHIP ORDINANCE, STORMWATER MANAGEMENT ORDINANCE.


**PROPERTY OWNERS CERTIFICATION**

THE LANDOWNER ACKNOWLEDGES THAT, PER THE PROVISIONS OF THE WESTTOWN TOWNSHIP STORMWATER MANAGEMENT ORDINANCE, IT IS UNLAWFUL TO MODIFY, REMOVE, FILL, LANDSCAPE, ALTER OR IMPAIR THE EFFECTIVENESS OF, OR PLACE ANY STRUCTURE, OTHER VEGETATION, YARD WASTE, BRUSH CUTTINGS, OR OTHER WASTE OR DEBRIS INTO ANY PERMANENT STORMWATER MANAGEMENT BMP OR CONVEYANCE DESCRIBED IN THIS O&M PLAN OR TO ALLOW THE BMP CONVEYANCE TO EXIST IN A CONDITION WHICH DOES NOT CONFORM TO THIS O&M PLAN, WITHOUT WRITTEN APPROVAL FROM THE TOWNSHIP. THE INDIVIDUAL LOT OWNER, HIS/HER HEIRS, ASSIGNS OR SUCCESSORS, SHALL BE RESPONSIBLE FOR THE PERPETUAL MAINTENANCE OF THE SAID FACILITIES. THE TOWNSHIP MAINTAINS THE RIGHT, BUT NOT THE RESPONSIBILITY, TO ENTER SAID PREMISES TO OBSERVE OR INSPECT THE FUNCTIONING OF THESE FACILITIES. IF THE PROPERTY OWNER, HIS/HER HEIRS, ASSIGNS OR SUCCESSORS FAILS IN ANY WAY TO MAINTAIN THE SAID FACILITIES OR CAUSES THESE FACILITIES TO BE ALTERED OR REMOVED, UPON WRITTEN NOTIFICATION BY THE TOWNSHIP, THE DEFECTS SHALL PROMPTLY BE CORRECTED BY PROPERTY OWNER. UPON THE OWNER'S FAILURE TO CORRECT THE DEFECTS WITHIN THE TIME SPECIFIED BY THE TOWNSHIP, THE OWNER, HIS/HER HEIRS, ASSIGNS OR SUCCESSORS DO HEREBY AUTHORIZE THE TOWNSHIP AND/OR THEIR CONTRACTOR TO ENTER UPON THE SAID PROPERTY AND CAUSE THE REPAIR, MAINTENANCE, AND/OR CORRECTION TO BE MADE. A LIEN MAY BE FILED AGAINST THE PROPERTY FOR THE COST OF ALL CORRECTIONS INCLUDING APPLICABLE ENGINEERING AND/OR ATTORNEY'S FEES. THE TOWNSHIP IS UNDER NO OBLIGATION TO TAKE ANY ACTION. ALL SUBSEQUENT REAL ESTATE TRANSACTIONS, THE EXISTENCE OF THESE STORMWATER FACILITIES AND THEIR MAINTENANCE RESPONSIBILITIES SHALL BE DISCLOSED TO THE NEW OWNERS. ANY REVISION TO THE APPROVED SWM SITE PLAN SHALL BE SUBMITTED TO THE TOWNSHIP ALONG WITH AN EROSION & SEDIMENTATION CONTROL PLAN FOR REVIEW AND APPROVAL.

ACT 287 SERIAL NUMBER 20180862796  
Edward B. Walsh & Associates, Inc. does not guarantee the accuracy of the locations for existing subsurface utility lines, structures, etc. shown on the plans, nor does E. B. Walsh & Assoc., Inc. guarantee that all subsurface utility lines, structures, etc. are shown.  
Contractor shall verify the location and elevations of all subsurface utility lines, structures, etc. before the start of work, by calling the Pennsylvania One Call System at 1-800-242-1776.

**UTILITIES NOTIFIED**  
VERIZON PENNSYLVANIA, INC.  
AQUA PENNSYLVANIA, INC.  
COMCAST CABLE COMMUNICATIONS, INC.  
WESTTOWN TOWNSHIP  
PECO ENERGY

UPI 67-4F-73




STORMWATER MANAGEMENT PLAN

1 7-26-18 REV. PER McCORMICK TAYLOR REVIEW OF JULY 11, 2018


PLAN OF SUBDIVISION  
OF  
UPI 67-4F-73

WESTTOWN TOWNSHIP CHESTER COUNTY, PA.  
Edward B. Walsh & Associates, Inc. Project- 4062  
CIVIL ENGINEERS & LAND SURVEYORS Date- 5-07-18  
LIONVILLE PROFESSIONAL CENTER Scale- 1"=30'  
125 Dowlin Forge Rd. Drawn- RBL  
Eaton, Pennsylvania 19341 Checked- AE  
Phone: 610-903-0060  
Fax: 610-903-0080 Sheet- 6 OF 8


Plotted: 7/26/2018 File: F:\JB\4062\4062-B5 Cahill sub.prn



LOT 2 BED DETAIL  
NOT TO SCALE



LOT 2 BED  
OUTLET DETAIL  
NOT TO SCALE



**RAIN GARDEN CONSTRUCTION SEQUENCE**

1. DELINEATE THE LIMIT OF THE RAIN GARDEN AS DEPICTED ON THE PLAN.
2. EXCAVATE THE SOIL WITH THE LIMITS OF THE RAIN GARDEN AND RIP THE SOIL AT THE BOTTOM OF THE EXCAVATED AREA WITH A RUBBER TIRE MACHINE TO LOOSEN THE SOIL.
3. BACKFILL THE EXCAVATED AREA WITH SOIL MIX. INSTALL THE SOIL IN 1 FT. LIFTS. TILL THE SOIL AFTER EACH LIFT.
4. AFTER SOIL PLACEMENT AND TILLING ARE COMPLETE, HAND RAKE AND INSTALL THE WETLAND SEED MIX AND LANDSCAPING IN ACCORDANCE WITH THE RAIN GARDEN LANDSCAPE PLAN AND MULCH ACCORDINGLY.
5. EVERY EFFORT MUST BE TAKEN TO MINIMIZE COPMPACTION WITH THE RAIN GARDEN AREAS.

**POST CONSTRUCTION MAINTENANCE**

- RAIN GARDEN**
- A. WHILE VEGETATION IS BEING ESTABLISHED PRUNING AND WEEDING MAY BE NECESSARY.
  - B. DETRITUS MUST BE REMOVED EVERY YEAR. PERENNIAL PLANTINGS MAY BE CUT DOWN AT THE END OF THE GROWING SEASON.
  - C. THE RAIN GARDEN MUST BE INSPECTED TWO(2) TIMES PER YEAR FOR SEDIMENT, SEDIMENT BUILD UP, EROSION AND VEGETATIVE CONDITIONS. ADDITIONALLY, TREES AND SHRUBS MUST BE INSPECTED TO EVALUATE THEIR HEALTH. IF FOUND TO BE UNHEALTHY THEY SHOULD BE REMOVED AND REPLACED.
  - D. ANY DEBRIS OR SEDIMENT BUILDUP MUST BE REMOVED AND SENT TO A DEP APPROVED FACILITY. IF DEWATERING IS NECESSARY THE WATER MUST BE DISCHARGED INTO A DEP APPROVED DEWATERING FACILITY. (DIRT BAG.)
  - E. MULCH SHOULD BE RE-SPREAD WHEN EROSION IS EVIDENT AND REPLENISHED AS NEEDED.
  - F. IF THE SYSTEM DOES NOT DRAIN FOR 72 HOURS FOLLOWING A RAIN EVENT IT IS CONSIDERED TO HAVE FAILED. THE BOTTOM MUST BE RE-TILLED TO LOOSEN THE SOIL. FOLLOWING THE TILLING THE AREAS MUST BE RE-TILLED TO LOOSEN THE SOIL. FOLLOWING THE TILLING AREAS MUST BE RE-SEEDED WITH THE SEED MIX SPECIFIED FOR THE RAIN GARDEN AREA.

**THE PCSWM PLAN/DESIGN PROVIDES THE FOLLOWING:**

1. PRESERVE THE INTEGRITY OF STREAM CHANNELS AND MAINTAIN AND PROTECT THE PHYSICAL, BIOLOGICAL AND CHEMICAL QUALITIES OF THE RECEIVING STREAM.
2. PREVENT AN INCREASE IN THE RATE OF STORMWATER RUNOFF.
3. MINIMIZE ANY INCREASE IN STORMWATER RUNOFF.
4. MINIMIZE IMPERVIOUS AREAS.
5. MAXIMIZE THE PROTECTION OF EXISTING DRAINAGE FEATURES AND EXISTING VEGETATION.
6. MINIMIZE LAND CLEARING AND GRADING.
7. MINIMIZE SOIL COMPACTION.
8. UTILIZES BMP'S THAT PREVENT OR MINIMIZE CHANGES IN STORMWATER RUNOFF.
9. UTILIZES BMP'S TO PREVENT THERMAL IMPACTS WITH THE STORMWATER DISCHARGE.

**PCSM SHORT TERM OPERATIONS AND MAINTENANCE REQUIREMENTS**

UNTIL THE PERMITEE OR CO-PERMITEE HAS RECEIVED WRITTEN APPROVAL OF A NOTICE OF TERMINATION, THE PERMITEE OR CO-PERMITEE WILL REMAIN RESPONSIBLE FOR COMPLIANCE WITH THE PERMIT TERMS AND CONDITIONS INCLUDING LONG-TERM OPERATION AND MAINTENANCE OF ALL PCSM BMP'S ON THE PROJECT SITE AND IS RESPONSIBLE FOR VIOLATIONS OCCURRING ON THE PROJECT SITE.

THE PERMITEE OR CO-PERMITEE SHALL BE RESPONSIBLE FOR LONG-TERM OPERATION AND MAINTENANCE OF PCSM BMP'S UNLESS A DIFFERENT PERSON IS IDENTIFIED IN THE NOTICE OF TERMINATION AND HAS AGREED TO LONG-TERM OPERATION AND MAINTENANCE OF PCSM BMP'S.

FOR ANY PROPERTY CONTAINING A PCSM BMP, THE PERMITEE OR CO-PERMITEE SHALL RECORD AN INSTRUMENT WITH THE RECORDER OF DEEDS WHICH WILL ASSURE DISCLOSURE OF THE PCSM BMP AND THE RELATED OBLIGATIONS IN THE ORDINARY COURSE OF A TITLE SEARCH OF THE SUBJECT PROPERTY. THE RECORDED INSTRUMENT MUST IDENTIFY THE PCSM BMP, PROVIDE FOR NECESSARY ACCESS RELATED TO LONG-TERM OPERATION AND MAINTENANCE OF PCSM BMP'S AND PROVIDE NOTICE THAT THE RESPONSIBILITY FOR LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMP IS A COVENANT THAT RUNS WITH THE LAND THAT IS BINDING UPON AND ENFORCEABLE BY SUBSEQUENT GRANTEE, AND PROVIDE PROOF OF FILING WITH THE NOTICE OF TERMINATION UNDER 102.7(b)(5) (RELATING TO PERMIT TERMINATION).

THE PERSON RESPONSIBLE FOR PERFORMING LONG-TERM OPERATION AND MAINTENANCE MAY ENTER INTO AN AGREEMENT WITH ANOTHER PERSON INCLUDING A CONSERVATION DISTRICT, NONPROFIT ORGANIZATION, MUNICIPALITY, AUTHORITY, PRIVATE CORPORATION OR OTHER PERSON, TO TRANSFER THE RESPONSIBILITY FOR PCSM BMP'S OR TO PERFORM LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMP'S LOCATED ON THE PROPERTY. A PERMITEE OR CO-PERMITEE THAT FAILS TO TRANSFER LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMP OR OTHERWISE FAILS TO COMPLY WITH THIS REQUIREMENT SHALL REMAIN JOINTLY AND SEVERALLY RESPONSIBLE WITH THE LANDOWNER FOR LONG TERM OPERATION AND MAINTENANCE OF THE PCSM BMP'S LOCATED ON THE PROPERTY.

**POST CONSTRUCTION REPORTING & RECORD KEEPING**

1. THE POST CONSTRUCTION STORMWATER PLAN, INSPECTION REPORTS AND MONITORING RECORDS SHALL BE AVAILABLE FOR REVIEW AND INSPECTION BY THE D.E.P. OR THE CONSERVATION DISTRICT.

**CONSTRUCTION DEBRIS HANDLING:**

1. CONSTRUCTION DEBRIS MUST BE STORED IN REUSE CONTAINERS FOR REMOVAL FROM THE SITE. THE CONTAINERS MUST BE PLACED IN ACCESSIBLE LOCATIONS.
2. NO DEBRIS MAY BE STORED/LEFT IN AREAS OR DEPRESSIONS ON THE SITE.
3. NO FUEL MAY BE STORED ON SITE.

**POST-CONSTRUCTION LONG TERM OPERATION AND MAINTENANCE OF STORMWATER FACILITIES:**

THE OPERATION AND MAINTENANCE OF THE BMP'S IS THE RESPONSIBILITY OF THE PROPERTY OWNER.

REGULAR REMOVAL OF LITTER AND DEBRIS WITHIN THE PROPERTY SHALL BE PERFORMED. SEDIMENT REMOVAL MUST BE PERFORMED WHEN IT HAS NO STANDING WATER. ACCUMULATED SEDIMENT MUST BE REMOVED AND DISPOSED OF IN AN APPROVED MANNER. IF THE AMOUNT OF SEDIMENT REQUIRES ITS TRANSPORT TO ANOTHER SITE, THE SITE MUST HAVE AN NPDES PERMIT.

1. ALL SEDIMENT MUST BE REMOVED WHEN NOTED IN THE BOTTOM OF STRUCTURES.
2. SEDIMENT REMOVAL MUST BE PERFORMED WHEN IT HAS NO STANDING WATER. ACCUMULATED SEDIMENT MUST BE REMOVED AND DISPOSED OF IN AN APPROVED MANNER. IF THE AMOUNT OF SEDIMENT REQUIRES ITS TRANSPORT TO ANOTHER SITE, THE SITE MUST HAVE AN NPDES PERMIT.
3. SYSTEM DEWATERING: SHOULD DEWATERING OF THE BASIN AREA BE REQUIRED, THE WATER MUST BE DISCHARGED TO A DEP APPROVED DEWATERING FACILITY (DIRT BAG OR EQUAL).
4. THE SYSTEM IS CONSIDERED FAILING IF IT DOES NOT DEWATER IN 72 HOURS. IF IT IS NOT DEWATERING THE WATER MUST BE CHECKED AND CLEARED OF ANY DEBRIS CLOGGING THE OUTLET SYSTEM.

REGULAR REMOVAL OF LITTER AND DEBRIS WITHIN THE PROPERTY SHALL BE PERFORMED. SEDIMENT REMOVAL MUST BE PERFORMED WHEN IT HAS NO STANDING WATER. ACCUMULATED SEDIMENT MUST BE REMOVED AND DISPOSED OF IN AN APPROVED MANNER. IF THE AMOUNT OF SEDIMENT REQUIRES ITS TRANSPORT TO ANOTHER SITE, THE SITE MUST HAVE AN NPDES PERMIT.

1. IF WATER IS STILL IN THE BOTTOM OF THE INLETS AT THE RECHARGE BED 72 HOURS AFTER A STORM EVENT, THE SYSTEM HAS FAILED AND MUST BE REPAIRED. THE SYSTEM MAY NEED TO BE EXCAVATED AND NEW STONE INSTALLED.
2. SHOULD DEWATERING BE REQUIRED, THE WATER MUST BE DISCHARGED TO A DEP APPROVED DEWATERING FACILITY (DIRTBAG OR EQUAL).
3. ANY DEBRIS OR TRASH IN THE BOTTOM OF THE INLETS MUST BE REMOVED AND DISPOSED OF PROPERLY.

- RAIN GARDEN:**
1. SYSTEM DEWATERING: IF WATER IS PONDED IN THE BOTTOM OF THE RAIN GARDEN BEYOND THREE BMP'S FOLLOWING A STORM EVENT THE GATE VALVE SHOULD BE OPENED TO ALLOW THE UNDERDRAIN TO FUNCTION. SHOULD DEWATERING OF THE PONDED AREA BE REQUIRED, THE WATER MUST BE DISCHARGED TO A DEP APPROVED DEWATERING FACILITY (DIRT BAG OR EQUAL).
  2. ANY DEBRIS THAT IS DEPOSITED IN THE RAIN GARDEN AREAS MUST BE RECYCLED OR REMOVED AND SENT TO AN APPROVED FACILITY.
  3. THE SYSTEMS MUST BE CHECKED ANNUALLY. SHOULD IT NOT DEWATER FOR 72 HOURS FOLLOWING A RAIN EVENT IT IS CONSIDERED TO BE FAILING AND THE BOTTOM MUST BE TILLED TO LOOSEN THE SOIL. FOLLOWING THE TILLING, THE DISTURBED AREA MUST BE STABILIZED WITH THE SEED MIX SPECIFIED FOR THE RAIN GARDEN AREA.

**GENERAL BMP AND E&S NOTES**

1. ALL OF THE BMP'S IDENTIFIED/PROPOSED ON THIS PLAN SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE DETAILS SHOWN HEREIN AND THE NOTES CONTAINED ON THE SHEET. THE WETLAND VEGETATION FOR THE BASINS SHALL NOT BE INSTALLED UNTIL 70% STABILIZATION OF THE TRIBUTARY AREA IS ACHIEVED AND THE CONVERSION TO ITS FINAL CONFIGURATION IS COMPLETE.
2. NO BMP SHALL BE INSTALLED UNTIL 70% VEGETATIVE COVER IS ACHIEVED. THE CONSERVATION DISTRICT SHALL BE NOTIFIED PRIOR TO THE INSTALLATION AND MUST CONCUR WITH THE 70% COVER BEFORE INSTALLATION IS BEGUN.
3. DURING CONSTRUCTION THE CONTRACTOR SHALL TAKE EVERY EFFORT TO KEEP SEDIMENT LADEN WATER OUT OF THE INFILTRATION BMP'S. IF ANY SEDIMENT LADEN WATER SHALL ENTER THE FACILITY, IMMEDIATE STEPS MUST BE UNDERTAKEN TO REMOVE IT. INCLUDING BUT NOT LIMITED TO CLEANING THE FABRIC AND STONE OR REPLACING IT DEPENDING ON THE SEVERITY OF THE INCURSION.
4. 50' BUFFER AREAS ARE REQUIRED AT THE STREAM CROSSING. ALL CLEARING, SOIL DISTURBANCES, EXCAVATION AND EQUIPMENT TRAFFIC SHOULD BE AVOIDED AND/OR MINIMIZED. ALL OTHER CONSTRUCTION OPERATIONS SHALL TAKE PLACE OUTSIDE THE BUFFER.

**INFILTRATION BED CONSTRUCTION SEQUENCE**

**(ENGINEERING OVERSIGHT REQUIRED)**


1. EXCAVATE AREA FOR BED TO SPECIFIED ELEVATION. CONTRACTOR MUST FOLLOW ALL NOTES AND DETAILS PROVIDED ON PCSWM PLAN REGARDING INSTALLATION.
2. CONTRACTOR SHALL BE VERY CAREFUL NOT TO RUN HEAVY EQUIPMENT OVER THE BOTTOM OF BED TO MINIMIZE POTENTIAL COMPACTION. SCARIFY BOTTOM.
3. PLACE GEOTEXTILE FABRIC ON BOTTOM AND ALL SIDES OF BED.
4. FILL BED WITH STONE TO THE ELEVATION OF THE INFLOW PIPES.
5. INSTALL INFLOW PIPES AND COMPLETE PLACEMENT OF STONE UP TO INVERT ELEVATION OF OUTLET STRUCTURE. INSTALL OUTLET STRUCTURE AND COMPLETE PLACEMENT OF STONE.
6. PLACE GEOTEXTILE OVER TOP OF BED WITH A MINIMUM OVERLAP OF 12 INCHES.
7. PLACE 1 FOOT OF COVER OVER ENTIRE BED AND INSTALL AN IMPERVIOUS GEOTEXTILE FABRIC AS SPECIFIED ON PLAN. BACKFILL THE REMAINDER OF THE BED. SEED MULCH AND STABILIZE IMMEDIATELY.

**INFILTRATION BED AND STORMWATER FACILITIES MAINTENANCE NOTES**

1. Regular removal of litter and debris within the property shall be performed. Stormwater facilities shall be inspected quarterly and any trash, debris, sediment, etc., shall be removed and properly disposed of.
2. Observations shall be made to determine the length of time needed for retained water to infiltrate into the soil after a storm event. The observations shall be made by reading the water level in the inlet box(es) of the underground system several times over a period of two (2) days after a large storm event. The first of these observations shall provide a record of how well the system is working when comparing future observations. Observations shall be made twice the first year and yearly thereafter.
3. Stormwater detention and retention basins or facilities shall be inspected by, or under the direction of, a registered professional engineer licensed in the Commonwealth of Pennsylvania on behalf of the applicant or responsible entity (including the Township Engineer for dedicated facilities) on the following basis:
  - a. Annually for the first five (5) years.
  - b. Once every three (3) years thereafter.
  - c. During or immediately after the cessation of a 100-year or greater storm event.
4. The stormwater management facilities shown on these plans, including storm inlets, storm drain pipes, underground detention systems, and roof drain connections, are permanent and are not to be removed. The Homeowner's Association, its successor or assigns shall assume the responsibility for perpetual maintenance of the said facilities. If the Homeowner's Association, its successor or assigns fails in any way to maintain the said facilities or causes the facilities to be altered or removed, upon written notification by the municipality, the defects shall be promptly corrected at the owner's expense. Upon the owner's failure to correct the defect within the time specified by the municipality, the owner, his successor or assigns do hereby authorize the municipality to enter upon the said property and cause the repairs maintenance and/or corrections to be made. A lien may be filed against the property for all costs of all corrections, including applicable engineering and/or attorney fees, although the municipality is under no obligation to take action. The permission granted herein shall constitute an access easement for maintenance purposes should some be necessary by the municipality in the sole opinion of the municipality. This maintenance responsibility shall be added into the deed.
5. All inflow and outflow points to the individual on-lot systems should be kept clear of leaves and other debris. Any leaves or debris will negatively impact the performance of these systems. All downspouts and overflow pipes should be kept in good working order.

**POST CONSTRUCTION INFILTRATION BED AND STORMWATER FACILITIES MAINTENANCE NOTES**

1. Regular removal of litter and debris within the property shall be performed. Stormwater facilities shall be inspected quarterly and any trash, debris, sediment, etc., shall be removed and properly disposed of.
2. Observations shall be made to determine the length of time needed for retained water to infiltrate into the soil after a storm event. The observations shall be made by reading the water level in the inlet box(es) of the underground system several times over a period of two (2) days after a large storm event. The first of these observations shall provide a record of how well the system is working when comparing future observations. Observations shall be made twice the first year and yearly thereafter.
3. Stormwater detention and retention basins or facilities shall be inspected by, or under the direction of, a registered professional engineer licensed in the Commonwealth of Pennsylvania on behalf of the applicant or responsible entity (including the Township Engineer for dedicated facilities) on the following basis:
  - a. Annually for the first five (5) years.
  - b. Once every three (3) years thereafter.
  - c. During or immediately after the cessation of a 100-year or greater storm event.
4. The stormwater management facilities shown on these plans, including storm inlets, storm drain pipes, underground detention systems, and roof drain connections, are permanent and are not to be removed. The Homeowner's Association, its successor or assigns shall assume the responsibility for perpetual maintenance of the said facilities. If the lot owner, his successor or assigns, fails in any way to maintain the said facilities or causes the facilities to be altered or removed, upon written notification by the municipality, the defects shall be promptly corrected at the owner's expense. Upon the owner's failure to correct the defect within the time specified by the municipality, the owner, his successor or assigns do hereby authorize the municipality to enter upon the said property and cause the repairs maintenance and/or corrections to be made. A lien may be filed against the property for all costs of all corrections, including applicable engineering and/or attorney fees, although the municipality is under no obligation to take action. The permission granted herein shall constitute an access easement for maintenance purposes should some be necessary by the municipality in the sole opinion of the municipality. This maintenance responsibility shall be added into the deed.
5. All inflow and outflow points to the individual on-lot systems should be kept clear of leaves and other debris. Any leaves or debris will negatively impact the performance of these systems. All downspouts and overflow pipes should be kept in good working order.



**Rain Garden Seed Mixture: ERNMX-120.**

Botanical Name	Common Name
Carex vulpinoidea	Fox Sedge
Elymus virginicus	Virginia Wild Rye
Verbena hastata	Blue Vervain
Carex crinita	Fringed (Nodding) Sedge
Carex lurida	Lurid (Shallow) Sedge
Glyceria grandis	American Mannagrass
Glyceria striata	Flow Mannagrass
Juncus effusus	Soft Rush
Scirpus cyperinus	Wool Grass
Sparganium americanum	Eastern Lesser Bur Reed
Sparganium eurycarpum	Giant Bur Reed
Scirpus atrovirens	Green Bulrush
Carex comosa	Cosmos (Bristly) Sedge
Carex gynandra	Nodding Sedge
Carex lupulina	Hop Sedge
Glyceria canadensis	Rattlesnake Grass

Seeding rate: 15 bulk lbs per acre or 1/3-1/2 lbs per 1,000 ft<sup>2</sup>.  
SEEDING SHALL TAKE PLACE BETWEEN APRIL 1 AND MAY 15 OR BETWEEN SEPT. 1 AND OCT. 15.

**ERNEST CONSERVATION SEED**  
9008 MERCER PIKE  
MEADVILLE, PA 16335  
www.ernestseed.com  
1-800-873-3321 Fax (814) 336-5191


	A	B	C	D	E	F	G	H				
	STONE UNDER PIPE (FT)	RECHARGER CHAMBER HEIGHT (IN)	TOP PIPE TO TOP BED (FT)	BOTTOM BED	BOTTOM PIPE	TOP PIPE	TOP OF BED	100 YR ELEV.	# OF ROWS	LENGTH OF ROWS (FT)	TOTAL LINER FEET	
BED 1	0.50'	2.5'	1.0'	372.50	373.0	375.50	376.50	376.0	2	30'	60'	

**RAIN GARDEN CONSTRUCTION SEQUENCE**

1. DELINEATE THE LIMIT OF THE RAIN GARDEN AS DEPICTED ON THE PLAN.
2. EXCAVATE THE SOIL WITH THE LIMITS OF THE RAIN GARDEN AND RIP THE SOIL AT THE BOTTOM OF THE EXCAVATED AREA WITH A RUBBER TIRE MACHINE TO LOOSEN THE SOIL.
3. BACKFILL THE EXCAVATED AREA WITH SOIL MIX. INSTALL THE SOIL IN 1 FT. LIFTS. TILL THE SOIL AFTER EACH LIFT.
4. AFTER SOIL PLACEMENT AND TILLING ARE COMPLETE, HAND RAKE AND INSTALL THE WETLAND SEED MIX AND LANDSCAPING IN ACCORDANCE WITH THE RAIN GARDEN LANDSCAPE PLAN AND MULCH ACCORDINGLY.
5. EVERY EFFORT MUST BE TAKEN TO MINIMIZE COPMPACTION WITH THE RAIN GARDEN AREAS.

**POST CONSTRUCTION MAINTENANCE**

- RAIN GARDEN**
- A. WHILE VEGETATION IS BEING ESTABLISHED PRUNING AND WEEDING MAY BE NECESSARY.
  - B. DETRITUS MUST BE REMOVED EVERY YEAR. PERENNIAL PLANTINGS MAY BE CUT DOWN AT THE END OF THE GROWING SEASON.
  - C. THE RAIN GARDEN MUST BE INSPECTED TWO(2) TIMES PER YEAR FOR SEDIMENT, SEDIMENT BUILD UP, EROSION AND VEGETATIVE CONDITIONS. ADDITIONALLY, TREES AND SHRUBS MUST BE INSPECTED TO EVALUATE THEIR HEALTH. IF FOUND TO BE UNHEALTHY THEY SHOULD BE REMOVED AND REPLACED.
  - D. ANY DEBRIS OR SEDIMENT BUILDUP MUST BE REMOVED AND SENT TO A DEP APPROVED FACILITY. IF DEWATERING IS NECESSARY THE WATER MUST BE DISCHARGED INTO A DEP APPROVED DEWATERING FACILITY. (DIRT BAG.)
  - E. MULCH SHOULD BE RE-SPREAD WHEN EROSION IS EVIDENT AND REPLENISHED AS NEEDED.
  - F. IF THE SYSTEM DOES NOT DRAIN FOR 72 HOURS FOLLOWING A RAIN EVENT IT IS CONSIDERED TO HAVE FAILED. THE BOTTOM MUST BE RE-TILLED TO LOOSEN THE SOIL. FOLLOWING THE TILLING THE AREAS MUST BE RE-TILLED TO LOOSEN THE SOIL. FOLLOWING THE TILLING AREAS MUST BE RE-SEEDED WITH THE SEED MIX SPECIFIED FOR THE RAIN GARDEN AREA.



BED #	INVERT OF OUTLET PIPE	OUTLET PIPE DIA (IN)	OUTLET PIPE LENGTH (FT)	SLOPE OF OUTLET PIPE	DOWNSTREAM INVERT OF OUTLET PIPE
1	376.17	4"	25'	.005	376.04

**FINAL CERTIFICATION**

THE PERMITEE SHALL INCLUDE WITH THE NOTICE OF TERMINATION "RECORD DRAWINGS" WITH A FINAL CERTIFICATION STATEMENT FROM A LICENSED PROFESSIONAL, WHICH READS AS FOLLOWS:

" I, \_\_\_\_\_ DO HEREBY CERTIFY PURSUANT TO THE PENALTIES OF 18 PA.C.S.A. SECTION 4904 TO THE BEST OF MY KNOWLEDGE, INFORMATION AND BELIEF THAT THE ACCOMPANYING RECORD DRAWINGS ACCURATELY REFLECT THE AS-BUILT CONDITIONS, ARE TRUE AND CORRECT, AND ARE IN CONFORMANCE WITH CHAPTER 102 OF THE RULES AND REGULATIONS OF THE DEPARTMENT OF ENVIRONMENTAL PROTECTION AND THAT THE PROJECT SITE WAS CONSTRUCTED IN ACCORDANCE WITH THE APPROVED PCSWM PLAN, ALL APPROVED PLAN CHANGES AND ACCEPTED CONSTRUCTION PRACTICES."











(1) THE PERMITEE SHALL RETAIN A COPY OF THE RECORD DRAWINGS AS A PART OF THE APPROVED PCSWM PLAN.  
(2) THE PERMITEE SHALL PROVIDE A COPY OF THE RECORD DRAWINGS AS PART OF THE APPROVED PCSWM PLAN TO THE PERSON IDENTIFIED IN THIS SECTION AS BEING RESPONSIBLE FOR THE LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMP'S.

**STORMWATER MANAGEMENT DETAILS**

1 7-26-18 REV. PER MCCORMICK TAYLOR REVIEW OF JULY 11, 2018

**PLAN OF SUBDIVISION OF UPI 67-4F-73**

WESTTOWN TOWNSHIP	CHESTER COUNTY, PA.
Edward B. Walsh & Associates, Inc. CIVIL ENGINEERS & LAND SURVEYORS LIONVILLE PROFESSIONAL CENTER 125 Dowlin Forge Rd. Eaton, Pennsylvania 19341 Phone: 610-903-0060 Fax: 610-903-0080	Project- 4062 Date- 5-07-18 Scale- N.T.S. Drawn- RBL Checked- AE Sheet- 7 OF 8
Plotted: 7/26/2018 P:\E\4062\4062-B5 Cahill sub.pro	



## DETAILS

1 7-26-18 REV. PER MCCORMICK TAYLOR REVIEW OF JULY 11, 2018

PLAN OF SUBDIVISION  
OF  
UPI 67-4F-73

WESTTOWN TOWNSHIP CHESTER COUNTY, PA.

Edward B. Walsh & Associates, Inc. Project- 4062

CIVIL ENGINEERS & LAND SURVEYORS Date- 5-07-18

LIONVILLE PROFESSIONAL CENTER Scale- N.T.S.

125 Dowlin Forge Rd. Drawn- RBL

Eston, Pennsylvania 19341 Checked- AE

Phone: 610-903-0060 Sheet- 8 OF 8

Fax: 610-903-0080

Plotted: 7/26/2018 File: F:\JB\4062\4062-B5 Cahill sub.prc